

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2943	1999-162 RS	COOK	48	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	54.8	54.8					
40600300	AGGREGATE (PRIME COAT)	TON	274	274					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	41	41					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	172	172					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1117	1117					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	397	397					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	630	630					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11518	11518					
42001300	PROTECTIVE COAT	SQ YD	330	330					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	261	261					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	134440	134440					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	990	990					
44002223	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 3/4"	SQ YD	1956	1956					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1444	1444					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	512	512					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	665	665					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	96	96					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	79	79					
60404940	FRAMES AND GRATES, TYPE 23	EACH	10	10					
60404950	FRAMES AND GRATES, TYPE 24	EACH	15	15					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	15	15					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	15	15					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19776	19776					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	450	450					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	55045	55045					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1228	1228					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3072	3072					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	580	580					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	450	450					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	55045	55045					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1228	1228					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3072	3072					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	580	580					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1344	1344					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1344	1344					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	718	718					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev. 5-27-08