

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	45	45				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26				
40600300	AGGREGATE (PRIME COAT)	TON	135	135				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SO YD	1120	1120				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	232	232				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6120	6120				
42001300	PROTECTIVE COAT	SO YD	45	45				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	60620	60620				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	120	120				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	1025	1025				
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SO FT	5	5				
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	110	110				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	202	202				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	104	104				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	242	242				
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	305	305				
* 55037800	STORM SEWERS TO BE CLEANED 12"	FOOT	940	940				
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13760	13760				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	775	775				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25990	25990				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	520	520				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	275	275				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	670	670				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	15900	15900				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	775	775				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25990	25990				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	520	520				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	275	275				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	670	670				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	715	715				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	648	648				
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2300	2300				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	282.7	282.7				

* SPECIALITY ITEMS
 ■ NON-PARTICIPATING ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU 1321: ILL 19 (IRVING PARK ROAD)
WISE ROAD TO COOK-DUPAGE COUNTY LINE
SUMMARY OF QUANTITIES