

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	(3W & 3264) RS-6	COOK	29	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 80% FED 20% STATE 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27				
40600300	AGGREGATE (PRIME COAT)	TON	133	133				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1246	1246				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1937	1937				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5600	5600				
42001300	PROTECTIVE COAT	SO YD	334	334				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2150	2150				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	7182	7182				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	59424	59424				
44000600	SIDEWALK REMOVAL	SO FT	2150	2150				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3426	3426				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	5766	5766				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	3025	3025				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	392	392				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	2287	2287				
55039700	STORM SEWERS TO BE CLEANED	FOOT	3000	3000				
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	15	15				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3				
60254100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	5	5				
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1				
60262700	INLETS TO BE RECONSTRUCTED	EACH	11	11				
60262900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	27	27				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 80% FED 20% STATE 1000-2A				
60264130	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	11	11				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	170	170				
60404940	FRAMES AND GRATES, TYPE 23	EACH	9	9				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	20	20				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	20	20				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14068	14068				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	826	826				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26632	26632				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2530	2530				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	320	320				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	732	732				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4689	4689				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	826	826				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26632	26632				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2530	2530				

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

4/8/2008 11:20:08 AM