



NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE FULL DEPTH PATCHES
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = W:\diststd\22x34\bd22.dgn	USER NAME = banks1	DESIGNED - R. SHAH	REVISED - A. ABBAS 01-20-98	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT			F.A.U. RTE. 3537	SECTION (3W+3264) 25-6	COUNTY COOK	TOTAL SHEETS 29	SHEET NO. 20	
		DRAWN -	REVISED - A. ABBAS 04-27-98					SCALE: NONE			SHEET NO. 1 OF 1 SHEETS		STA. TO STA.
		PLOT SCALE = 50.000' / IN.	REVISOR - R. BORO 01-01-07		CONTRACT NO. 60872								
		PLOT DATE = 3/25/2008	DATE - 10-25-94		REVISED - R. BORO 09-04-07								