

CONTRACT # 60C32

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000	I000			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	101	101				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	557		557			△
20800150	TRENCH BACKFILL	CU YD	37		37			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	60		60			
25200110	SODDING, SALT TOLERANT	SO YD	60		60			
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SO YD	360		360			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20				
40600300	AGGREGATE (PRIME COAT)	TON	100	100				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	33	33				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	3	3				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	425	425				△
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4		4			△
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2044	2040	4			△
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SO YD	310		310			
44000100	PAVEMENT REMOVAL	SO YD	310		310			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	24190	24190				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	180		180			
44002236	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 9"	SO YD	817		817			△
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	300	300				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	25	25				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	375	375				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	912	912				

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000	I000			
50300300	PROTECTIVE COAT	SO YD	40		40			
50800105	REINFORCEMENT BARS	POUND	55		55			△
54248510	CONCRETE COLLAR	CU YD	0.5		0.5			△
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	6		6			
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	26		26			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	180		180			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				△
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5			△
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14480	14240	240			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	568.2	508.2	60			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30100	26100	4000			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2940	2540	400			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2800	2500	300			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	388		388			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	508.2	508.2				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26100	26100				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2540	2540				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2500	2500				

△ Rev. 6-3-08

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES