CONTRACT NO. 60C42

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	531-2.1-1	COOK	10	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

SUMMARY OF QUANTITIES

URBAN 100% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: SFTY-2A					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	45	45					
20200100	EARTH EXCAVATION	CU YD	121	121					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	29.5	29.5					
20900110	POROUS GRANULAR BACKFILL	CU YD	9	9					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	177	177					
25000312	SEEDING, CLASS 4A	ACRE	0.04	0.04					
25100630	EROSION CONTROL BLANKET	SQ YD	177	177					
28000400	PERIMETER EROSION BARRIER	FOOT	40	40					
50102400	CONCRETE REMOVAL	CU YD	6.4	6.1					
50200100	STRUCTURE EXCAVATION	CU YD	26.8	26.8					
50300225	CONCRETE STRUCTURES	CU YD	6	6					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	710	710					
51100300	SLOPE WALL 6 INCH	SQ YD	9.5	9.5					
51205200	TEMPORARY SHEET PILING	SQ FT	1420	1420					
60107700	PIPE UNDERDRAINS 6"	FOOT	18	18					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	65	65					
63200310	GUARDRAIL REMOVAL	FOOT	65	65					
66400305	CHAIN LINK FENCE, 6'	FOOT	80	80					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	125	125					
X0322879	GRADING AND SHAPING FORESLOPES	SQ YD	177	177					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 4/8/2008

4/8/2008
pw:\\dot-dist1-pw01.bentley.com:dot-dist1-pw01-d1\Documents\Projects\Design\Sheets\Summary of Quantities.dgn