



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 4, 2008

SUBJECT: FAP Route 339  
Project ACNHF-0339 (025)  
Section 2007-017 RS  
Cook County  
Contract No. 60C72  
Item No. 249, June 13, 2008 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 and 2 of the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 73 to the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60C72

State Job # - C-91-258-07  
 PPS NBR - 1-76753-0000  
 County Name - COOK- -  
 Code - 31 - -  
 District - 1 - -  
 Section Number - 2007-017RS

Project Number  
 ACNHF-0339/025/

Route  
 FAP 339

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
X0322256	TEMP INFO SIGNING	SQ FT	102.800					
X4067107	POL LB MM IL4.75 N50	TON	2,016.000					
Z0018500	DRAINAGE STR CLEANED	EACH	56.000					
Z0048665	RR PROT LIABILITY INS	L SUM	1.000					
* Z0064800	SELECTIVE CLEARING	UNIT	15.000					
Z0076600	TRAINEES	HOUR	1,500.000		0.800		1,200.000	
40600200	BIT MATLS PR CT	TON	20.000					
40600300	AGG PR CT	TON	51.000					
40600400	MIX CR JTS FLANGEWYS	TON	15.000					
40600895	CONSTRUC TEST STRIP	EACH	2.000					
40600982	HMA SURF REM BUTT JT	SQ YD	360.000					
40601005	HMA REPL OVER PATCH	TON	620.000					
40603595	P HMA SC "F" N90	TON	4,705.000					
42001300	PROTECTIVE COAT	SQ YD	4,108.000					
42400200	PC CONC SIDEWALK 5	SQ FT	125.000					
* 42400800	DETECTABLE WARNINGS	SQ FT	24.000					
44000159	HMA SURF REM 2 1/2	SQ YD	48,000.000					
			* REVISED : JUNE 2, 2008					

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60C72

State Job # - C-91-258-07  
 PPS NBR - 1-76753-0000  
 County Name - COOK- -  
 Code - 31 - -  
 District - 1 - -  
 Section Number - 2007-017RS

Project Number  
 ACNHF-0339/025/

Route  
 FAP 339

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000600	SIDEWALK REM	SQ FT	125.000				
44001700	COMB C C&G REM & REPL	FOOT	2,150.000				
44002224	HMA RM OV PATCH 6	SQ YD	1,845.000				
44201753	CL D PATCH T2 9	SQ YD	887.000				
44201757	CL D PATCH T3 9	SQ YD	548.000				
44201759	CL D PATCH T4 9	SQ YD	410.000				
* 48101200	AGGREGATE SHLDS B	TON	100.000				
55039700	SS CLEANED	FOOT	561.000				
60251740	CB ADJ NEW T24F&G	EACH	1.000				
60300305	FR & LIDS ADJUST	EACH	9.000				
60300310	FR & LIDS ADJUST SPL	EACH	17.000				
60406000	FR & LIDS T1 OL	EACH	4.000				
60406100	FR & LIDS T1 CL	EACH	10.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70102625	TR CONT & PROT 701606	L SUM	1.000				
			* REVISED : JUNE 2, 2008				

ICRR REQUIREMENTS ..... 65  
SELECTIVE CLEARING ..... 73

Revised 06/04/2008

**SELECTIVE CLEARING**

Effective: February 8, 2007

Description. This work shall consist of extensive removal and disposal of shrubs, brush, debris (including rocks, bottles, etc.) and selected trees up to six (6) inches (150 mm) in diameter. All trees and shrubs to be saved shall be carefully protected as provided by Article 201.05 of the Standard Specifications. Locations for Selective Clearing and vegetation to be cleared or saved shall be designated by the Engineer.

The undesirable trees and brush (Siberian Elm, European Buckhorn, Mulberry, etc.) shall be cut flush with the ground and all stubs or stumps shall be treated with a re-sprout herbicide approved by the Engineer to prevent re-growth from the stumps. Trees of Tree of Heaven shall not be cut off as specified above, but shall be pulled or grubbed in such a manner as to insure complete removal. Branches on remaining trees shall be pruned off up to 6 feet (2 meters) from the ground.

All cleared areas shall be graded, trimmed, smoothed, and finished uniformly to the satisfaction of the Engineer with equipment approved by the Engineer. Disposal of material shall be done in accordance with Article 202.03.

Method of Measurement. Selective Clearing will be measured in units of 1,000 square feet (90 square meters). Areas not meeting the satisfaction of the Engineer shall not be measured for payment. Plan quantities are estimates only. Actual quantities will be measured in place. Agreement to plan quantities will not be allowed.

Basis of Payment. This work will be paid for at the contract unit price per unit for SELECTIVE CLEARING.

Added 06/04/2008