

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
339	2007-017RS	COOK	33	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
D-91-258-07				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20				
40600300	AGGREGATE (PRIME COAT)	TON	51	51				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	360	360				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	620	620				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4705	4705				
42001300	PROTECTIVE COAT	SO YD	4108	4108				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	125	125				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	48000	48000				
44000600	SIDEWALK REMOVAL	SO FT	125	125				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2150	2150				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	1845	1845				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	887	887				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	548	548				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	410	410				
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	561	561				
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	9				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4	4				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2442	2442				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	754	754				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25485	25485				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1940	1940				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	820	820				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	507	507				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	754	754				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25485	25485				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1940	1940				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	820	820				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	507	507				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1306	1306				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1306	1306				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1611	1611				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2016	2016				
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	56	56				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
* Z0076600	TRAINEES	HOUR	1500	1500				

© 1980
* - Specialty Items
NP = Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

4/16/2008 10:00 AM C:\P\2007\017RS\1000-2A.DWG