

SUMMARY OF QUANTITIES

ITEM	PAY ITEM DESCRIPTION	UNIT	URBAN		
			100% STATE TOTAL QUANTITY	ROADWAY QUANTITY 1000-2A	BRIDGE QUANTITY X071-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2	
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	4	4	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	298	298	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	932	932	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,036	2,036	
50102400	CONCRETE REMOVAL	CU YD	120		120
50157300	PROTECTIVE SHIELD	SQ YD	1,362		1,362
50300255	CONCRETE SUPERSTRUCTURE	CU YD	132		132
50300260	BRIDGE DECK GROOVING	SQ YD	1,130		1,130
50300300	PROTECTIVE COAT	SQ YD	1,630		1,630
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5,880		5,880
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	27		27
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	15,980		15,980
52000110	PREFORMED JOINT STRIP SEAL	FOOT	488		488
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	27		27
52100520	ANCHOR BOLTS, 1"	EACH	50		50
52100540	ANCHOR BOLTS, 1 1/2"	EACH	4		4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,605	1,605	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	425	425	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	481	481	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	20	20	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	43	43	
* 78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	398	398	
* 78006130	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	173	173	
* 78006140	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	149	149	
* 78006180	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	41	41	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	59	59	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	EACH	44	44	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	103	103	
X0320887	POLYMER CONCRETE	CU FT	14		14
X0321743	SILICONE JOINT SEALER, 1"	FOOT	83		83
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	1,058		1,058
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	80		80
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	818		818
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	333	333	
X4421000	PARTIAL DEPTH PATCHING	TON	51	51	
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	452	452	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1,016		1,016
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	3		3
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	32		32
X0326096	ALUMINUM RAILING, SPECIAL	FOOT	26		26

*Specialty Items

H:\Jobs\2006\2006-3028-43\CAD\DOT Trans\dm\00\Ssummary of Quantities-43_V8.dgn 3/25/2008 2:58:58 PM



GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC.
CHICAGO, ILLINOIS

FILE NAME =	USER NAME = #USER#	DESIGNED - MW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - EUB	REVISED -			541	9 HB-1-1	LAKE	26	3	
	PLOT SCALE = #SCALE#	CHECKED - RJS	REVISED -			CONTRACT NO. 60D90					
	PLOT DATE = 3/25/2008	DATE - 3/27/08	REVISED -			SCALE: NTS	SHEET NO. OF 26 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		