

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	QUANTITIES	I000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26					
40600300	AGGREGATE (PRIME COAT)	TON	129	129					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	322	322					
40600990	TEMPORARY RAMP	SO YD	322	322					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	786	786					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6315	6315					
42001300	PROTECTIVE COAT	SO YD	282	282					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	64433	64433					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1447	1447					
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	2338	2338					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1006	1006					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	716	716					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	521	521					
<input type="checkbox"/> 55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	23	23					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	QUANTITIES	I000-2A					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10671	10671					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	695	695					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27944	27944					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1756	1756					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1576	1576					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	580	580					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	14810	14810					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	695	695					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27944	27944					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1756	1756					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1576	1576					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	580	580					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	956	956					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	813	813					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	2304	2304					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	4650	4650					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2537	2537					
<input type="checkbox"/> Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	31	31					
<input checked="" type="checkbox"/> Z0076600	TRAINERS	HOUR	2000	2000					

* SPECIALITY ITEMS
 NON-PARTICIPATING ITEMS
 @ Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 F.A.P. 029 (US 12/20 (95TH ST.))
 US 45 (LA GRANGE RD.)
 TO I-294 (TRI-STATE TOLLWAY)

4/3/2008 4:20:03 PM C:\PLOT\60D94.DWG