

CONTRACT NO. 60D96

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY	PARKING	PARKING		
				1000-2A 80% FED. 20% STATE	LANES 50% STATE 50% VILLAGE OF OAKLAWN Y025	LANES 50% STATE 50% VILLAGE EVERGRN PRK Y025		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	187	180	2	5		
40600300	AGGREGATE (PRIME COAT)	TON	617	595	5	17		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	142	136	2	4		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	5995	5995				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	4620	4620				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	30120	29115	215	790		
42001300	PROTECTIVE COAT	SO YD	940	940				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	350	350				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	307210	297010	2159	8041		
44000600	SIDEWALK REMOVAL	SO FT	350	350				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4200	4200				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	1650	1650				
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SO YD	15460	15460				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	24	24				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	7806	7806				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	3184	3184				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	975	975				
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1200	1200				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	32	32				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2				
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	33	33				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	381	381				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	101	101				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9				
67100100	MOBILIZATION	L SUM	1	1				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY	PARKING	PARKING		
				1000-2A 80% FED. 20% STATE	LANES 50% STATE 50% VILLAGE OF OAKLAWN Y025	LANES 50% STATE 50% VILLAGE EVERGRN PRK Y025		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	54120	54120				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2622	2622				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	113715	13715				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	18700	18700				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4185	4185				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6285	6285				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3145	3145				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	82510	82510				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2622	2622				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	113715	13715				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	18700	18700				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4185	4185				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6285	6285				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	3145	3145				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5100	5100				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4270	4270				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	8733	8733				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	12285	11880	85	320		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

NP= Non-Participating  
\* Specialty Items Rev.