

SUMMARY OF QUANTITIES			100% STATE	URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	114	114					
40600300	AGGREGATE (PRIME COAT)	TON	571	571					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	43	43					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	816	816					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	730	730					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	14408	14408					
42001300	PROTECTIVE COAT	SO YD	19	19					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	142735	142735					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1800	1800					
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	2173	2173					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	30	30					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	470	470					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	97	97					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	221	221					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	32	32					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	606	606					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	292	292					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	425	425					
55039700	STORM SEWERS TO BE CLEANED	FOOT	7000	7000					
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	30	30					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	23	23					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					

SUMMARY OF QUANTITIES			100% STATE	URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5466	5466					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2269	2269					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20,465	20,465					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11062	11062					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	585	585					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	978	978					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1268	1268					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	607	607					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2269	2269					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,465	20,465					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	11062	11062					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	585	585					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	978	978					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1268	1268					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1377	1377					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1600	1600					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	7405	7405					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6175	6175					
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	150	150					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	340	340					
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	60	60					

2/20/2008

\* - Specialty Items

REV.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
ILL 53 (BOLINGBROOK DRIVE)  
JOLIET RD. TO DUPAGE CO. LINE