

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
870	534 RS-4	DuPage	24	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26					
40600300	AGGREGATE (PRIME COAT)	TON	130	130					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	395	395					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	178	178					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6390	6390					
42001300	PROTECTIVE COAT	SO YD	154	154					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	65200	65200					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	865	865					
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	530	530					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	15	15					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	205	205					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	190	190					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	154	154					
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	10	10					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	31	31					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9426	9426					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	951	951					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20022	20022					

SUMMARY OF QUANTITIES			100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3753	3753					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	67	67					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	677	677					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3142	3142					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	951	951					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20022	20022					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3753	3753					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	67	67					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	677	677					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	507	507					
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	450	450					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2722	2722					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	2738	2738					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	21	21					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

2/20/2008 2:58:03 PM C:\pccollect\shil100888.rdw