

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				80% FEDERAL / 20% STATE								50% STATE 50% HARVEY		100% HARVEY			
				ROADWAY	RAILROAD	RR BRIDGE 016-2755 2819 & 2822	INTERMODAL BRIDGE 016-2820 & 2821	RETAINING WALL	TRAFFIC SIGNAL PARK AVE.	TRAFFIC SIGNAL INTER- CONNECT	NEW SIDEWALK	WATER- MAIN	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.			
J000-2A	K000-5B	X631-5B	X781-2A	Y007	Y031-1F	Y031-1F	SFTY-1B	Y060	Y030-1E	Y031-3D							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	257		257												
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1											
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1										
50200100	STRUCTURE EXCAVATION	CU YD	10408.4			4616.5	2114	3677.9									
50300225	CONCRETE STRUCTURES	CU YD	6984.1		195	2954.9	1984.2	1250									
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1066			550	516										
50300260	BRIDGE DECK GROOVING	SQ YD	1533				1533										
50300300	PROTECTIVE COAT	SQ YD	1683				1683										
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	2120.1				2120.1										
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1											
50800105	REINFORCEMENT BARS	POUND	133190		18990	50900	63300										
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,591,870		19130	752,900	688370	131470									
50800515	BAR SPLICERS	EACH	1491			408	819	264									
50901720	BICYCLE RAILING	FOOT	1280					1280									
50901750	PARAPET RAILING	FOOT	330				330										
50901765	PIPE HANDRAIL, SPECIAL	FOOT	928			640		288									
51500100	NAME PLATES	EACH	5			3	2										
51603000	DRILLED SHAFT IN SOIL	CU YD	2739		222	1245	1272										
51604000	DRILLED SHAFT IN ROCK	CU YD	314.2		13	161.2	140										
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	44				44										
52100520	ANCHOR BOLTS, 1"	EACH	96				96										
52100530	ANCHOR BOLTS, 1 1/4"	EACH	472			472											
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	645		645												

- * DENOTES SPECIALTY ITEM
- Y080
- △ SFTY-3N
- NON-PARTICIPATING



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM LEXINGTON AVE TO FISK AVE

SUMMARY OF QUANTITIES

DATE 02/21/08
DRAWN BY J.R.P.
CHECKED BY M.R.F.