

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	2008-001VB	COOK	579	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60E10

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE																		
				80% FEDERAL / 20% STATE							50% STATE 50% HARVEY	100% HARVEY										
				ROADWAY	RAILROAD	RR BRIDGE 016-2755 2819 & 2822	INTERMODAL BRIDGE 016-2820 & 2821	RETAINING WALL	TRAFFIC SIGNAL PARK AVE.	TRAFFIC SIGNAL INTER- CONNECT	NEW SIDEWALK	WATER- MAIN	LIGHTING	TRAFFIC SIGNAL EVP EQUIP.								
				J000-2A	K000-5B	X631-5B	X781-2A	Y007	Y031-1F	Y031-1F	SFTY-1B	Y060	Y030-1E	Y031-3D								
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	1817	1817																		
M4060300	AGGREGATE (PRIME COAT)	M TON	8	8																		
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	88	88																		
M4062125	LEVELING BINDER (MACHINE METHOD), N50	M TON	133	133																		
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	11	11																		
M4063080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	M TON	226	226																		
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	290	290																		
M4063595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	M TON	21	21																		
M4202265	PORTLAND CEMENT CONCRETE PAVEMENT 260MM (JOINTED)	SQ M	20056	20056																		
M4205200	PROTECTIVE COAT	SQ M	23957	23957																		
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	75	75																		
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SQ M	1544	1410								134										
M4245000	TEMPORARY SIDEWALK	SQ M	422	422																		
M4400785	HOT-MIX ASPHALT SURFACE REMOVAL, 85MM	SQ M	2668	2668																		
M4402000	PAVEMENT REMOVAL	SQ M	16370	16370																		
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	480	480																		
M4402020	CURB REMOVAL	METER	112	112																		
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	2709	2709																		
M4402050	SIDEWALK REMOVAL	SQ M	902	902																		
M4428025	CLASS D PATCHES, TYPE I, 225MM	SQ M	218	218																		
M4428225	CLASS D PATCHES, TYPE II, 225MM	SQ M	218	218																		

- DENOTES SPECIALTY ITEM
- Y080
- △ SFTY-3N
- NON-PARTICIPATING

URS 100 S. WACKER DR., SUITE 500
CHICAGO, ILLINOIS 60606
TEL. (312) 939-1000
FAX (312) 939-4198

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 FROM LEXINGTON AVE TO FISK AVE

SUMMARY OF QUANTITIES

DATE 02/21/08

DRAWN BY J.R.P.
CHECKED BY M.R.F.

\$FILES\$
 \$DATE\$
 \$TIME\$