

MCHD CLAIM NO. 735298

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	MCHD SFTY-2A				
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	1				
50157300	PROTECTIVE SHIELD	SO YD	205	205				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	55.8	55.8				
50300260	BRIDGE DECK GROOVING	SO YD	167	167				
50300300	PROTECTIVE COAT	SO YD	235.6	235.6				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	9720	9720				
50500505	STUD SHEAR CONNECTORS	EACH	375	375				
50501110	STRUCTURAL STEEL REMOVAL	POUND	9720	9720				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13,830	13,830				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	75	75				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	5	5				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	90	90				
* 72000300	SIGN PANEL - TYPE 3	SO FT	88	88				
* 73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	13	13				
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	250	250				
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" x 6" x 4"	EACH	4	4				
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" x 10" x 6"	EACH	3	3				
* 81800340	AERIAL CABLE, 3-1/C NO. 8 WITH MESSENGER WIRE	FOOT	50	50				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SO FT	48	48				
* X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	300	300				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
* X8170100	ELECTRIC CABLE IN CONDUIT, REMOVE ALL CONDUCTORS	FOOT	300	300				
* X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING	EACH	7	7				
* XX003079	REMOVE JUNCTION BOX	EACH	3	3				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	MCHD SFTY-2A				
* XX004046	AERIAL CABLE REMOVAL	FOOT	250	250				
* XX004308	LIQUID TIGHT FLEXIBLE METALLIC CONDUIT, 1 INCH	FOOT	50	50				
Z0003480	BEAM REPOSITIONING	EACH	4	4				
Z0003600	BEAM STRAIGHTENING	L SUM	1	1				
Z0040330	PIN AND LINK PLATE REPLACEMENT	EACH	5	5				
* X0326097	ELECTRIC CABLE IN CONDUIT, (EPR-TYPE RHW), 3-1/C NO. 10, 1/C NO. 10 GROUND	FOOT	300	300				

4/30/2008

* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
115TH ST. (EB) OVER FAI 94
SN. 016-2042