



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE FULL DEPTH PATCHES
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = K:\diststd22x34\bd22.dgn	USER NAME = bauerdl	DESIGNED - R. SHAH	REVISED - A. ABBAS 01-20-98	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT	F.A.U. RTE. 3512	SECTION 86-RS-3	COUNTY COOK	TOTAL SHEETS 35	SHEET NO. 21	
PLOT SCALE = 50,000' / IN.	CHECKED -	REVISED - R. BORO 01-01-07	REVISED - A. ABBAS 04-27-98			SCALE: NONE		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.	
PLDT DATE = 3/11/2008	DATE - 10-25-94	REVISED - R. BORO 09-04-07	BD400-04 (BD-22)			CONTRACT NO.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			