

LANDSCAPING SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	114R-1	WILL	355	19
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

LOCATION	TOPSOIL FURNISH AND PLACE, 4"	TOPSOIL FURNISH AND PLACE, 8"	TOPSOIL FURNISH AND PLACE, 12"	SEEDING CLASS 2A	SEEDING CLASS 4	SEEDING CLASS 5A	SODDING, SALT TOLERANT	EROSION CONTROL BLANKET	COMPOST FURNISH AND PLACE, 4"	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	INTERSEEDING CLASS 4
	SQ YD	SQ YD	SQ YD	ACRES	ACRES	ACRES	SQ YD	SQ YD	SQ YD	POUND	POUND	POUND	ACRE
IL ROUTE 59													
STA 3032+25.77 TO STA 3040+50	2292	196			0.04	0.04	2284	194	204	32	32	32	
STA 3040+50 TO STA 3055+00	3751	632		0.08	0.57	0.57	1221	6679	2755	139	139	139	0.73
STA 3055+00 TO STA 3069+50	570	4762		0.45			3138	2178		79	79	79	
STA 3069+50 TO STA 3084+00	432	4385					4868			60	60	60	
STA 3084+00 TO STA 3098+00	631	5796	279	0.12			6145	581		87	87	87	
STA 3098+00 TO STA 3112+50	3777	3061	1429	0.55			5614	2662		119	119	119	
STA 3112+50 TO STA 3127+00	5558	1720	814	0.63			5031	3049		119	119	119	
STA 3127+00 TO STA 3141+50	1893	4698	730	0.65			4159	3146		110	110	110	
STA 3141+50 TO STA 3153+00	1939	3413	968	1.02			1372	4937		109	109	109	
STA 3153+00 TO STA 3167+50	1300	4360	2062	0.84			3641	4066		121	121	121	
STA 3167+50 TO STA 3182+00	544	5107	855	0.11			5982	532		84	84	84	
STA 3182+00 TO STA 3196+25	319	3680	404				4403			55	55	55	
TOTALS	23006	41810	7541	4.50	0.75	0.75	47857	28024	2959	1134	1134	1134	0.75

DRAINAGE AND UTILITY STRUCTURAL REMOVAL

STATION	OFFSET	REMOVING INLETS EACH	REMOVING CATCH BASINS EACH	REMOVING MANHOLES EACH	REMOVING INLETS BOXES EACH	CONCRETE HEADWALL REMOVAL EACH
IL ROUTE 59						
STA. 3033+34.0	39.6' LT		1			
STA. 3033+49.3	33.0' RT	1				
STA. 3033+51.2	31.8' LT	1				
STA. 3035+16.2	50.7' LT	1				
STA. 3035+48.3	34.1' LT	1				
STA. 3035+50.2	27.6' LT			1		
STA. 3035+53.8	24.4' RT	1				
STA. 3035+58.7	47.8' LT	1				
STA. 3035+85.2	37.4' LT		1			
STA. 3037+53.6	37.1' RT	1				
STA. 3037+56.0	10.4' LT			1		
STA. 3037+56.1	5.1' LT			1		
STA. 3037+61.1	13.2' LT	1				
STA. 3038+46.2	9.1' LT	1				
STA. 3038+89.8	37.9' LT			1		
STA. 3039+12.2	27.1' LT	1				
STA. 3039+66.9	71.2' LT	1				
STA. 3039+78.4	29.4' LT	1				
STA. 3040+33.9	9.7' LT			1		
STA. 3040+34.1	0.1' RT	1				
STA. 3048+84.3	28.1' LT					1
STA. 3049+47.3	20.1' LT		1			
STA. 3053+55.2	51.3' LT					1
STA. 3054+03.2	28.1' LT			1		
STA. 3055+80.4	28.2' LT			1		
STA. 3056+07.8	31.1' LT			1		
STA. 3058+03.3	33.5' LT			1		
STA. 3060+93.0	27.8' RT	1				
STA. 3061+06.6	35.1' LT			1		
STA. 3063+57.5	38.0' RT		1			
STA. 3063+58.7	30.2' RT	1				
STA. 3064+30.2	36.6' LT			1		
STA. 3065+51.7	36.8' RT		1			
STA. 3067+82.8	41.2' LT			1		
STA. 3067+83.5	32.9' LT	1				
STA. 3067+98.0	28.3' RT			1		
STA. 3071+28.5	48.5' LT			1		
STA. 3073+26.5	48.5' LT			1		
STA. 3074+52.4	46.7' RT			1		
STA. 3074+78.8	48.6' LT		1			
STA. 3076+51.5	48.7' LT			1		
STA. 3077+01.5	48.7' LT			1		
STA. 3077+01.5	42.7' LT	1				
STA. 3078+61.5	50.7' LT			1		
STA. 3078+62.5	32.9' LT	1				
STA. 3078+96.5	50.5' LT			1		
STA. 3079+61.5	50.5' LT	1				
STA. 3081+78.4	58.4' RT		1			
STA. 3081+85.8	94.9' LT		1			
STA. 3082+93.6	41.8' LT			1		
STA. 3083+05.6	50.3' RT	1				
STA. 3084+23.0	37.1' RT	1				
STA. 3084+28.2	27.7' LT	1				
STA. 3084+29.5	42.5' LT		1			
STA. 3085+28.5	28.0' LT	1				
STA. 3085+29.6	40.2' LT		1			
STA. 3086+78.0	28.1' LT	1				
STA. 3086+79.0	40.3' LT		1			
STA. 3088+53.3	27.8' LT	1				
STA. 3091+17.3	51.5' RT		1			
STA. 3092+51.3	52.0' RT		1			
STA. 3092+53.5	41.0' LT			1		
STA. 3093+11.5	37.8' LT		1			
STA. 3093+26.2	32.4' LT		1			
STA. 3094+05.4	49.9' RT		1			
STA. 3094+98.0	49.7' RT	1				
STA. 3095+46.9	32.7' RT			1		
STA. 3095+58.2	35.3' RT			1		
STA. 3099+56.1	31.2' RT			1		
STA. 3125+16.0	41.5' LT		1			
STA. 3135+02.3	73.6' RT			1		
STA. 3135+32.2	92.6' RT			1		
STA. 3135+40.2	32.9' RT			1		

DRAINAGE AND UTILITY STRUCTURAL REMOVAL (CONTINUED)

STATION	OFFSET	REMOVING INLETS EACH	REMOVING CATCH BASINS EACH	REMOVING MANHOLES EACH	REMOVING INLETS BOXES EACH	CONCRETE HEADWALL REMOVAL EACH
IL ROUTE 59						
STA. 3135+41.3	136.4' RT		1			
STA. 3135+44.6	51.6' LT			1		
STA. 3135+45.1	144.4' LT		1			
STA. 3154+20.5	43.1' RT		1			
STA. 3155+04.6	30.4' RT		1			
STA. 3155+04.9	55.3' LT			1		
STA. 3155+70.1	96.2' RT			1		
STA. 3163+11.6	26.6' RT				1	
STA. 3172+17.7	74.4' LT	1				
STA. 3172+63.6	71.1' LT		1			
STA. 3173+63.1	40.7' RT			1		
STA. 3174+51.3	35.5' LT		1			
STA. 3187+41.8	42.8' LT			1		
STA. 3187+41.4	52.7' LT		1			
STA. 3187+62.5	43.0' LT	1				
STA. 3187+73.9	56.5' LT	1				
STA. 3187+79.4	97.6' RT	1				
STA. 3187+83.3	106.7' LT	1				
STA. 3188+44.6	103.5' LT	1				
STA. 3188+55.5	56.1' LT	1				
STA. 3188+64.3	45.2' LT	1				
THEODORE STREET						
STA. 98+43.5	31.5' RT	1				
STA. 98+43.9	20.9' LT	1				
STA. 102+15.7	21.58' LT	1				
TOTALS		37	24	32	2	2

STORM SEWER TO BE CLEANED

LOCATION	LENGTH FOOT
IL ROUTE 59	
STA 3032+25.77 TO STA 3040+50	106
STA 3040+50 TO STA 3055+00	0
STA 3055+00 TO STA 3069+50	0
STA 3069+50 TO STA 3084+00	1175
STA 3084+00 TO STA 3098+00	469
STA 3098+00 TO STA 3112+50	0
STA 3112+50 TO STA 3127+00	0
STA 3127+00 TO STA 3141+50	1111
STA 3141+50 TO STA 3153+00	0
STA 3153+00 TO STA 3167+50	0
STA 3167+50 TO STA 3182+00	536
STA 3182+00 TO STA 3193+25	902
BLACK ROAD	
STA 13+00 TO STA 13+75	74
THEODORE STREET	
STA 97+45 TO STA 98+50	0
STA 101+50 TO STA 103+00	196
TOTALS	4569

PIPE UNDERDRAINS 4"

LOCATION	LENGTH FOOT
IL ROUTE 59	
STA 3032+25.77 TO STA 3040+50	1430
STA 3040+50 TO STA 3055+00	3235
STA 3055+00 TO STA 3069+50	3019
STA 3069+50 TO STA 3084+00	2829
STA 3084+00 TO STA 3098+00	2825
STA 3098+00 TO STA 3112+50	3002
STA 3112+50 TO STA 3127+00	3010
STA 3127+00 TO STA 3141+50	3199
STA 3141+50 TO STA 3153+00	2306
STA 3153+00 TO STA 3167+50	2925
STA 3167+50 TO STA 3182+00	2901
STA 3182+00 TO STA 3193+25	2594
TOTAL	33275

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
**LANDSCAPING, DRAINAGE AND UTILITY
 STRUCT. REMOVAL, SS TO BE CLEANED,
 AND PIPE UNDERDRAIN SCHEDULES**

DATE 3/18/08
 DRAWN BY MJG
 CHECKED BY VJD

SCALE: NONE

DATE: _____ BY: _____
 PLAN: _____
 CHECKED: _____
 DATE: _____ BY: _____
 PROFILE: _____

DATE: _____ BY: _____
 PROFILE: _____