



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2008

SUBJECT: FAP Route 338
Project ACNHF-0338 (034)
Section (113 & 114)R-5
Will County
Contract No. 62417
Item No. 236, June 13, 2008 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 5, 9, 10, 11, 14, 15, 17, 18, 20, 21, 22, 24 & 25 of the Schedule of Prices.
2. Revised page 2 of the Special Provisions.
3. Revised sheets 4, 5, 7 – 11, 13, 14, 17, 23 – 26, 30, 34, 35, 37, 40, 44 – 51, 70, 74, 75, 96 – 100, 109, 119 – 124, 138 – 148, 227, 232, 234, 235, 367, 372 – 377, 381, 383 & 387 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in cursive script, appearing to read 'Ted B. Walschleger', followed by the initials 'P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* X0323863	SS WM REQ T2 12"	FOOT	543.000				
* X0323889	SS WM REQ T2 18"	FOOT	124.000				
X0323973	SED CONT SILT FENCE	FOOT	19,217.000				
X0323974	SED CONT SILT FN MAIN	FOOT	19,217.000				
X0323988	TEMP SOIL RETEN SYSTM	SQ FT	360.000				
X0324439	DI W MN FIT 4 PLUG	EACH	2.000				
X0324449	DI WT MNF MJ 8X6 HTEE	EACH	1.000				
X0324688	DI WAT MNF 12 11.25B	EACH	1.000				
X0324689	DI WAT MNF 12 22.5B	EACH	3.000				
X0324919	PLUG MECH JOINT 12"	EACH	5.000				
X0324927	TEE DIMJ 12X12	EACH	2.000				
X0324930	DUCT IRON SLEEVE, 12"	EACH	1.000				
X0324931	DUCT IRON SLEEVE, 8"	EACH	6.000				
X0325705	RE-OPTIMIZE SIG SYS 2	EACH	1.000				
X0325737	TEMP TR SIGNAL TIMING	EACH	2.000				
			* REVISED : JUNE 3, 2008				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
20100110	TREE REMOV 6-15	UNIT	937.000					
20100210	TREE REMOV OVER 15	UNIT	932.000					
20101100	TREE TRUNK PROTECTION	EACH	102.000					
20101200	TREE ROOT PRUNING	EACH	102.000					
20101300	TREE PRUN 1-10	EACH	81.000					
20101350	TREE PRUN OVER 10	EACH	21.000					
* 20200100	EARTH EXCAVATION	CU YD	20,455.000					
20201200	REM & DISP UNS MATL	CU YD	8,041.000					
* 20400800	FURNISHED EXCAV	CU YD	71,779.000					
20700420	POROUS GRAN EMB SUBGR	CU YD	6,651.000					
* 20800150	TRENCH BACKFILL	CU YD	11,160.000					
21101615	TOPSOIL F & P 4	SQ YD	27,161.000					
21101630	TOPSOIL F & P 8	SQ YD	53,471.000					
21101645	TOPSOIL F & P 12	SQ YD	7,359.000					
21301052	EXPLOR TRENCH 52	FOOT	200.000					
			* REVISED : JUNE 3, 2008					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
35501308	HMA BASE CSE 6	SQ YD	640.000					
35501316	HMA BASE CSE 8	SQ YD	2,444.000					
40300100	BIT MATLS PR CT	GALLON	1,020.000					
40600300	AGG PR CT	TON	20.000					
40603310	HMA SC "C" N50	TON	552.000					
40603340	HMA SC "D" N70	TON	270.000					
40603595	P HMA SC "F" N90	TON	182.000					
42000416	PCC PVT 9 3/4 JOINTD	SQ YD	89,112.000					
42001300	PROTECTIVE COAT	SQ YD	25,796.000					
42300200	PCC DRIVEWAY PAVT 6	SQ YD	177.000					
42300400	PCC DRIVEWAY PAVT 8	SQ YD	1,245.000					
42400200	PC CONC SIDEWALK 5	SQ FT	66,021.000					
* 42400410	PC CONC SIDEWALK 8	SQ FT	6,270.000					
42400800	DETECTABLE WARNINGS	SQ FT	322.000					
44000100	PAVEMENT REM	SQ YD	62,592.000					
			* REVISED : JUNE 3, 2008					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
54213669	PRC FLAR END SEC 24	EACH	7.000					
54213675	PRC FLAR END SEC 30	EACH	3.000					
54247110	GRATING-C FL END S 18	EACH	1.000					
54247130	GRATING-C FL END S 24	EACH	3.000					
54247150	GRATING-C FL END S 30	EACH	3.000					
* 55019500	SS 1 RCP CL 4 12	FOOT	1,044.000					
* 55019600	SS 1 RCP CL 4 15	FOOT	13.000					
* 55019900	SS 1 RCP CL 4 24	FOOT	727.000					
55020100	SS 1 RCP CL 3 30	FOOT	766.000					
55020300	SS 1 RCP CL 3 36	FOOT	327.000					
* 55021600	SS 2 RCP CL 3 12	FOOT	7,380.000					
* 55021700	SS 2 RCP CL 3 15	FOOT	1,467.000					
* 55021800	SS 2 RCP CL 3 18	FOOT	1,125.000					
* 55021900	SS 2 RCP CL 3 21	FOOT	621.000					
* 55022000	SS 2 RCP CL 3 24	FOOT	1,931.000					
			* REVISED : JUNE 3, 2008					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55022200	SS 2 RCP CL 3 30	FOOT	816.000				
* 55022400	SS 2 RCP CL 3 36	FOOT	1,827.000				
55022500	SS 2 RCP CL 3 42	FOOT	190.000				
55034700	SS 1 RCEP S53 R34	FOOT	325.000				
55037600	SS CLEANED 8	FOOT	74.000				
55037800	SS CLEANED 12	FOOT	432.000				
55037900	SS CLEANED 15	FOOT	429.000				
55038000	SS CLEANED 18	FOOT	1,306.000				
55038200	SS CLEANED 24	FOOT	312.000				
55038400	SS CLEANED 30	FOOT	128.000				
55038700	SS CLEANED 42	FOOT	670.000				
* 55100200	STORM SEWER REM 6	FOOT	30.000				
* DELETED							
55100400	STORM SEWER REM 10	FOOT	65.000				
55100500	STORM SEWER REM 12	FOOT	540.000				
55100700	STORM SEWER REM 15	FOOT	424.000				
				* REVISED : JUNE 3, 2008			

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
59300100	CONTR LOW-STRENG MATL	CU YD	450.000					
60109510	P UNDR FAB LINE TR 4	FOOT	24,475.000					
60200105	CB TA 4 DIA T1F OL	EACH	1.000					
60200805	CB TA 4 DIA T8G	EACH	11.000					
* 60201320	CB TA 4 DIA T21F&G	EACH	38.000					
* 60201330	CB TA 4 DIA T23F&G	EACH	3.000					
* 60201340	CB TA 4 DIA T24F&G	EACH	98.000					
60207605	CB TC T8G	EACH	16.000					
60218400	MAN TA 4 DIA T1F CL	EACH	26.000					
60221000	MAN TA 5 DIA T1F OL	EACH	1.000					
60221100	MAN TA 5 DIA T1F CL	EACH	27.000					
60223800	MAN TA 6 DIA T1F CL	EACH	11.000					
60224446	MAN TA 7 DIA T1F CL	EACH	4.000					
60236200	INLETS TA T8G	EACH	8.000					
* 60237460	INLETS TA T23F&G	EACH	6.000					
			* REVISED : JUNE 3, 2008					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
70102550	TR CONT-PROT TEMP DET	EACH	1.000				
70103816	TR CONT SURVEILLANCE	CAL MO	21.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	84.000				
* 70300100	SHORT-TERM PAVT MKING	FOOT	12,270.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	364.000				
70300220	TEMP PVT MK LINE 4	FOOT	63,764.000				
70300240	TEMP PVT MK LINE 6	FOOT	1,043.000				
70300260	TEMP PVT MK LINE 12	FOOT	264.000				
70300280	TEMP PVT MK LINE 24	FOOT	268.000				
70300510	PAVT MARK TAPE T3 L&S	SQ FT	1,386.000				
70300520	PAVT MARK TAPE T3 4	FOOT	119,096.000				
70300540	PAVT MARK TAPE T3 6	FOOT	5,026.000				
70300550	PAVT MARK TAPE T3 8	FOOT	510.000				
70300560	PAVT MARK TAPE T3 12	FOOT	1,992.000				
70300570	PAVT MARK TAPE T3 24	FOOT	788.000				
			* REVISED : JUNE 3, 2008				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62417

State Job # - C-91-124-02
 PPS NBR - 1-70859-0100
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (113&114)R-5

Project Number
 ACNHF-0338/034/

Route
 FAP 338

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
* 70301000	WORK ZONE PAVT MK REM	SQ FT	66,475.000					
70400100	TEMP CONC BARRIER	FOOT	670.000					
70400200	REL TEMP CONC BARRIER	FOOT	910.000					
72000100	SIGN PANEL T1	SQ FT	794.000					
72000200	SIGN PANEL T2	SQ FT	20.000					
72800100	TELES STL SIN SUPPORT	FOOT	485.500					
72900100	METAL POST TY A	FOOT	968.000					
72900200	METAL POST TY B	FOOT	548.000					
78000100	THPL PVT MK LTR & SYM	SQ FT	184.000					
78000200	THPL PVT MK LINE 4	FOOT	7,612.000					
78000400	THPL PVT MK LINE 6	FOOT	549.000					
78000600	THPL PVT MK LINE 12	FOOT	456.000					
78000650	THPL PVT MK LINE 24	FOOT	15.000					
* 78005100	EPOXY PVT MK LTR-SYM	SQ FT	582.000					
* 78005110	EPOXY PVT MK LINE 4	FOOT	38,722.000					
			* REVISED : JUNE 3, 2008					

COMPLETION DATE PLUS WORKING DAYS

Effective: September 30, 1985

Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on, June 30, 2010 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within **10** working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.

WINTER WORK

No adjustment will be made in the contract unit prices if winter work is necessary to meet the required completion dates specified in the contract.

WORK RESTRICTIONS

The Contractor shall be subject to the following work restrictions:

- Permanent or night-time closures will not be allowed on IL Route 59 during Year 1 (2008) of construction. During Year 1 of construction, only temporary lane closures will be allowed on IL Route 59 for temporary pavement construction, temporary traffic signal, and temporary drainage. Lane closure will not be permitted during the hours of 6:00 a.m. to 9:00 a.m. and 3:00 p.m. to 6:00 p.m. Monday through Friday. All lane closure signs shall not be erected any earlier than one-half (1/2) hour before the starting hours listed above. Also, these signs should be taken down within one-half (1/2) hour after the closure is removed. The Contractor will not be allowed to proceed with any construction operations on the roadway of Illinois Route 59 that may require overnight lane closures, lane shifts and/or shoulder closures prior to March 1, 2009.
- The Contractor shall also complete all tree removal and clearing within 30 Calendar days after start of work in year 1 (2008). This completion will allow the utilities to relocate their facilities in a timely manner. Article 108.09 of the Standard Specifications shall apply to the completion date.
- The Contractor will not be allowed to proceed with any Stage III construction operations on the roadway of Illinois Route 59 that may require overnight lane closures, lane shifts and/or shoulder closures prior to March 1, 2010. The Contractor shall open to traffic two northbound lanes and two southbound lanes. Permanent or night-time closures will not be allowed on IL Route 59 between October 30, 2009 and March 1, 2010.

INTERIM COMPLETION DATE FOR STAGES 1 AND 2

The contractor shall complete all work in Stages 1 and 2 and their sub-stages by October 30, 2009. The work to be completed in Stages 1 and 2 and their sub-stages is as follows:

- Installation of all proposed drainage structures, storm sewers and water mains.
- Construction of the proposed pavement and curb and gutters for all side roads.
- Construction of the proposed pavement for the IL Route 59 northbound and southbound travel lanes and outside curb and gutters.

Revised 06/05/2008