

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	7
STA.		TO STA.		
FED. ROAD DIST. NO.		BLDG.	FAP 338 (IL RTE. 59)	

SUMMARY OF QUANTITIES													
CODE NO	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS									
				ROADWAY & DRAINAGE 80% FED 20% STATE	TRAFFIC SIGNALS IL 59 @ FRASER/ 80% FED 10% STATE 10% VILLAGE	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE	WATER MAIN/ SANITARY SEWER 100% VILLAGE	SIDEWALK 50% STATE 50% VILLAGE	
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y060	SFTY-HB
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3									
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	7									
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	3	3									
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	1	1									
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	3	3									
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	3	3									
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	1044	1044									
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	13	13									
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	727	727									
55020100	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	766	766									
55020300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	327	327									
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	7,380	7,380									
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	1,467	1,467									
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	1,125	1,125									
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21"	FOOT	621	621									
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	1,931	1,931									
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	816	816									
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	1,827	1,827									

- * SPECIAL PROVISION
- SPECIALITY ITEM
- ∞ CONSTRUCTION CODE Y080
- VILLAGE = VILLAGE OF PLAINFIELD
- COUNTY = WILL COUNTY

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM

Rev. 5-30-08