CONTRACT NO. 62417

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
338	(113 & 114) R-5	WILL	525	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FAP 338 (IL RTE. 59)		

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED 20% STATE J000-2A	TRAFFIC SIGNALS IL 59 @ FEENEY/ FRASER 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS IL 59 @ RENWICK 80% FED 10% STATE 10% COUNTY Y031-1F	TRAFFIC SIGNALS IL 59 @ FORT BEGGS 80% FED 13.3% STATE 6.7% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS TEMPORARY INTERCONNECT 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	WATER MAIN/ SANITARY SEWER 100% VILLAGE Y060	SIDEWALK 50% STATE 50% VILLAGE SFTY-1B
*	X0336855	PRECAST CONCRETE BOX CULVERT END SECTIONS 5' X 3'	EACH	2	2								
*	X0712400	TEMPORARY PAVEMENT	SQ YD	33,360	33,360								
*	X2111000	TOPSOIL EXCAVATION	CU YD	18,585	18,585								
*	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	16	16								
*	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	30	30								
*	X4023000	TEMPORARY ACCESS (ROAD)	EACH	14	14								
*	X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	3	3								
*	X4200500	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	2,765	2,765								
*	X6064500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (TEMPORARY)	FOOT	165	165								
O *	X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2	2								
*	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	27	27								
O *	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	3		1	1	1					
O *	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	3		1	1	1					
O *	X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	7,628					7,628				
O *	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2,037.5							2,037.5		
O *	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	873		290	313	270					
O *	X8900015	TEMPORARY TRAFFIC SIGNAL INTERCONNECTION SYSTEM	L SUM	1						1			
*	X0326000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (TEMPORARY)	FOOT	1,519	1,519								
*	X0326001	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12 (TEMPORARY)	FOOT	356	356								
*	X0326002	STORM SEWERS JACKED IN PLACE, 12" (SPECIAL)	FOOT	129	129								
*	X0323863	STORM SEWERS, (WATER MAIN REQUIREMENTS), TYPE 2, 12"	FOOT	543	462							81	
*	X0323889	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 18"	FOOT	124	106							18	
*	X0326003	TEMPORARY MANHOLE	EACH	1	1								
*	56104000	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 10"	FOOT	22								22	

* SPECIAL PROVISION

O SPECIALITY ITEM

∞ CONSTRUCTION CODE Y080

VILLAGE = VILLAGE OF PLAINFILED
COUNTY = WILL COUNTY

Rev. 5-30-08

Rev. 04-18-08 JCM

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

SCALE NONE
DATE MARCH 18, 2008
DRAWN BY JMH
CHECKED BY JCM