

FAP NO.	SECTION	COUNTY	TOTAL PAGES	SHEET NO.
338	(113 & 114) R-5	WILL	525	30
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FAP 338 (IL RTE. 59)		

EARTHWORK VOLUME (CU YD)

Station To Station	Length	Earth Excavation (Suitable Cut)					Earth Excavation (15% S.F.) Used for Embankment					Embankment (Suitable Fill)					Earthwork Balance (cu yd) (+) - Wastage / (-) - Shortage					Topsoil Excavation					Removal & Disposal of Unsuitable Material					Porous Granular Embankment Subgrade (PGES)						
		Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre-Stage	Stage 1	Stage 2	Stage 3	Stage 4		
ROLF ROAD:																																						
300+50	300+75	25	0	0	6	0	0	0	0	0	0	0	0	23	0	0	0	0	-18	0	0	0	0	10	0	0	0	0	0	0	0	0	0	0	0	0	0	0
300+75	301+00	25	0	0	12	0	0	0	0	0	0	0	5	0	0	0	0	5	0	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
301+00	301+25	25	0	0	21	0	0	0	0	0	0	0	18	0	0	0	0	2	0	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
301+25	301+50	25	0	0	27	0	0	0	0	0	0	0	23	0	0	0	0	1	0	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
SUB-TOTAL			0	0	66	0	0	0	0	0	0	0	56	0	0	0	0	31	0	0	0	0	28	0	0	0	0	0	0	0	0	0	0	0	0	0		
TOTAL (ROLF)					66								56					31					28													0		
DAYFIELD DRIVE:																																						
398+75	399+00	25	0	47	0	0	0	0	0	40	0	0	0	0	0	0	3	0	0	0	0	13	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
399+00	399+25	25	0	39	0	0	0	0	0	33	0	0	0	0	0	0	8	0	0	0	0	25	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
SUB-TOTAL			0	85	0	0	0	0	0	72	0	0	0	0	0	0	11	0	0	0	0	62	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
TOTAL (DAYFIELD)				85						72						11					62		30													0		
WEDGEWOOD COURT:																																						
598+60	598+75	15	0	11	0	0	0	0	0	9	0	0	0	0	0	1	0	0	0	0	8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
598+75	599+00	25	0	19	0	0	0	0	0	16	0	0	0	0	0	4	0	0	0	0	12	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
599+00	599+25	25	0	20	0	0	0	0	0	17	0	0	0	0	0	5	0	0	0	0	12	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
599+25	599+50	25	0	12	0	0	0	0	0	10	0	0	0	0	0	17	0	0	0	0	-7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
SUB-TOTAL			0	62	0	0	0	0	0	53	0	0	0	0	0	28	0	0	0	0	25	0	0	0	0	33	0	0	0	0	0	0	0	0	0	0		
TOTAL (WEDGEWOOD)				62						53					28					25		33														0		
COMMERCIAL DRIVE:																																						
800+75	801+05	30	0	0	0	0	0	0	0	0	0	0	0	135	0	0	0	0	-134	0	0	0	0	11	0	0	0	0	0	0	0	0	0	0	0	0		
801+05	801+25	20	0	0	0	0	0	0	0	0	0	0	0	42	0	0	0	0	-42	0	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0			
801+25	801+50	25	0	0	4	0	0	0	0	4	0	0	0	18	0	0	0	0	-14	0	0	0	7	0	0	0	0	0	0	0	0	0	0	0	0	0		
801+50	801+75	25	0	0	22	0	0	0	0	19	0	0	0	2	0	0	0	0	17	0	0	6	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
801+75	802+25	50	0	0	78	0	0	0	0	66	0	0	0	2	0	0	0	0	65	0	0	10	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
802+25	802+50	25	0	0	26	0	0	0	0	22	0	0	0	0	0	0	0	0	22	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
SUB-TOTAL			0	0	131	0	0	0	0	111	0	0	0	0	199	0	0	0	-88	0	0	0	43	0	0	0	0	0	0	0	0	0	0	0	0	0		
TOTAL (COMM'L DR.)				131						111				199				-88				43														0		
NORMAN AVENUE:																																						
100+50	100+75	25	0	0	5	0	0	0	0	4	0	0	0	29	0	0	0	0	-25	0	0	0	19	0	0	0	0	0	0	0	0	0	0	0	0	0		
100+75	101+00	25	0	0	11	0	0	0	0	9	0	0	0	10	0	0	0	0	-1	0	0	0	17	0	0	0	0	0	0	0	0	0	0	0	0	0		
101+00	101+25	25	0	0	18	0	0	0	0	16	0	0	0	5	0	0	0	0	11	0	0	0	17	0	0	0	0	0	0	0	0	0	0	0	0	0		
101+25	101+50	25	0	0	28	0	0	0	0	24	0	0	0	2	0	0	0	0	22	0	0	0	12	0	0	0	0	0	0	0	0	0	0	0	0	0		
101+50	101+75	25	0	0	32	0	0	0	0	27	0	0	0	1	0	0	0	0	26	0	0	0	9	0	0	0	0	0	0	0	0	0	0	0	0	0		
101+75	102+00	25	0	0	32	0	0	0	0	27	0	0	0	1	0	0	0	0	26	0	0	0	9	0	0	0	0	0	0	0	0	0	0	0	0	0		
102+00	102+22	22	0	0	25	0	0	0	0	21	0	0	0	0	0	0	0	0	21	0	0	0	5	0	0	0	0	0	0	0	0	0	0	0	0			
SUB-TOTAL			0	0	151	0	0	0	0	128	0	0	0	0	49	0	0	0	80	0	0	0	86	0	0	0	0	0	0	0	0	0	0	0	0	0		
TOTAL (NORMAN)				151						128				49				80				86														0		
ROBERTS AVENUE:																																						
200+50	200+75	25	0	0	22	0	0	0	0	18	0	0	0	3	0	0	0	0	15	0	0	0	14	0	0	0	0	0	0	0	0	0	0	0	0	0		
200+75	201+00	25	0	0	21	0	0	0	0	18	0	0	0	1	0	0	0	0	17	0	0	0	10	0	0	0	0	0	0	0	0	0	0	0	0	0		
201+00	201+10	10	0	0	7	0	0	0	0	6	0	0	0	0	0	0	0	0	6	0	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
SUB-TOTAL			0	0	50	0	0	0	0	42	0	0	0	0	5	0	0	0	38	0	0	0	26	0	0	0	0	0	0	0	0	0	0	0	0	0		
TOTAL (ROBERTS)				50						42				5				38				26														0		
TEMPORARY FILL FOR WINTER SHUTDOWN					2148					0				0					-2148				0															
PROJECT TOTAL					20,455					15,561				85,192					-71,779				18,585													8,001		



REVISIONS	
NAME	DATE
ADDENDUM B	05-27-08

ILLINOIS DEPARTMENT OF TRANSPORTATION
 DISTRICT NO. 1 SCHAUMBURG

EARTHWORK SCHEDULE

SCALE NONE
 DATE MARCH 18, 2008

DRAWN BY RTA
 CHECKED BY JCM