

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	57
STA.	TO STA.			
FED. ROAD DIST. NO.	ALIGNMENT	FAP 338 (IL RTE. 59)		

EROSION CONTROL QUANTITY SCHEDULE

			25100630	28000250	28000300	28000510	X0323973
STATION OR BEGINNING DESCRIPTION	STATION OR ENDING DESCRIPTION	OFFSET (LT/RT)	EROSION CONTROL BLANKET (SY)	TEMPORARY EROSION CONTROL SEEDING (LB)	TEMPORARY DITCH CHECKS (EACH)	INLET FILTERS (EACH)	SEDIMENT CONTROL, SILT FENCE
PRE-STAGE							
STA 3193+25	BRIDGE	LT	4405	92	8	-	-
STA 3193+25	RIVERWALK DRIVE	RT	-	-	-	-	-
RIVERWALK DRIVE	BRIDGE	RT	-	-	-	-	-
BRIDGE	DAYFIELD AVE	LT	15466	320	8	17	3112
BRIDGE	ROLF ROAD	RT	2886	60	3	-	143
ROLF ROAD	DAYFIELD AVE. (FUTURE)	RT	9572	198	7	-	1897
DAYFIELD DR.	WEDGEWOOD CT.	LT	3834	79	4	6	352
WEDGEWOOD CT.	FRASER / FEENEY ROAD	LT	4155	86	0	7	753
DAYFIELD DR.	FRASER / FEENEY ROAD	RT	8149	169	3	2	987
FRASER / FEENEY ROAD	RENWICK ROAD	LT	4136	86	4	5	403
FRASER / FEENEY ROAD	RENWICK ROAD	RT	9502	198	6	2	1587
RENWICK ROAD	FORT BEGGS ROAD	LT	480	10	-	-	-
RENWICK ROAD	ROBERTS AVE	RT	6920	143	1	20	1533
FORT BEGGS DR.	UNION ST.	LT	-	-	-	-	-
ROBERTS AVE.	UNION ST.	RT	1489	31	-	4	1056
UNION ST.	STA 3330+80	RT	870	20	-	2	343
PRE-STAGE SUBTOTAL			71864	1492	44	65	12166

EROSION CONTROL QUANTITY SCHEDULE

			25100630	28000250	28000300	28000510	X0323973
STATION OR BEGINNING DESCRIPTION	STATION OR ENDING DESCRIPTION	OFFSET (LT/RT)	EROSION CONTROL BLANKET (SY)	TEMPORARY EROSION CONTROL SEEDING (LB)	TEMPORARY DITCH CHECKS (EACH)	INLET FILTERS (EACH)	SEDIMENT CONTROL, SILT FENCE
STAGE 1							
STA 3193+25	BRIDGE	LT	4368	91	-	11	-
STA 3193+25	RIVERWALK DRIVE	RT	2404	50	-	7	744
RIVERWALK DRIVE	BRIDGE	RT	1675	35	-	1	252
BRIDGE	DAYFIELD AVE	LT	12584	260	2	31	-
BRIDGE	ROLF ROAD	RT	-	-	-	-	-
ROLF ROAD	DAYFIELD AVE. (FUTURE)	RT	-	-	-	-	-
DAYFIELD DR.	WEDGEWOOD CT.	LT	2824	58	2	11	85
WEDGEWOOD CT.	FRASER / FEENEY ROAD	LT	3650	76	2	3	566
DAYFIELD DR.	FRASER / FEENEY ROAD	RT	867	18	-	-	-
FRASER / FEENEY ROAD	RENWICK ROAD	LT	8545	178	-	25	1918
FRASER / FEENEY ROAD	RENWICK ROAD	RT	-	-	-	-	-
RENWICK ROAD	FORT BEGGS ROAD	LT	5812	121	5	23	2764
RENWICK ROAD	ROBERTS AVE	RT	-	-	-	-	-
FORT BEGGS DR.	UNION ST.	LT	734	15	-	1	351
ROBERTS AVE.	UNION ST.	RT	-	-	-	-	-
UNION ST.	STA 3330+80	RT	-	-	-	-	-
STAGE 1 SUBTOTAL			43463	902	11	113	6680

EROSION CONTROL QUANTITY SCHEDULE

			25100630	28000250	28000300	28000510	X0323973
STATION OR BEGINNING DESCRIPTION	STATION OR ENDING DESCRIPTION	OFFSET (LT/RT)	EROSION CONTROL BLANKET (SY)	TEMPORARY EROSION CONTROL SEEDING (LB)	TEMPORARY DITCH CHECKS (EACH)	INLET FILTERS (EACH)	SEDIMENT CONTROL, SILT FENCE
STAGE 2							
STA 3193+25	BRIDGE	LT	-	-	-	-	-
STA 3193+25	RIVERWALK DRIVE	RT	-	-	-	-	-
RIVERWALK DRIVE	BRIDGE	RT	2086	43	-	5	-
BRIDGE	DAYFIELD DR.	LT	-	-	-	5	-
BRIDGE	ROLF ROAD	RT	2835	59	-	6	-
ROLF ROAD	DAYFIELD AVE. (FUTURE)	RT	9967	206	-	22	-
DAYFIELD DR.	WEDGEWOOD CT.	LT	-	-	-	0	-
WEDGEWOOD CT.	FRASER / FEENEY ROAD	LT	-	-	-	1	-
DAYFIELD DR.	FRASER / FEENEY ROAD	RT	8347	173	-	17	150
FRASER / FEENEY ROAD	RENWICK ROAD	LT	-	-	-	2	-
FRASER / FEENEY ROAD	RENWICK ROAD	RT	8347	174	-	36	110
RENWICK ROAD	FORT BEGGS ROAD	LT	712	15	-	-	-
RENWICK ROAD	ROBERTS AVE	RT	5937	124	-	25	50
FORT BEGGS DR.	UNION ST.	LT	-	-	-	-	-
ROBERTS AVE.	UNION ST.	RT	930	20	-	8	61
UNION ST.	STA 3330+80	RT	563	12	-	4	-
STAGE 2 SUBTOTAL			39724	826	0	131	371

STAGE 3 - NO QUANTITY

EROSION CONTROL QUANTITY SCHEDULE

			25100630	28000250	28000300	28000510	X0323973
STATION OR BEGINNING DESCRIPTION	STATION OR ENDING DESCRIPTION	OFFSET (LT/RT)	EROSION CONTROL BLANKET (SY)	TEMPORARY EROSION CONTROL SEEDING (LB)	TEMPORARY DITCH CHECKS (EACH)	INLET FILTERS (EACH)	SEDIMENT CONTROL, SILT FENCE
STAGE 4							
STA 3260+00	STA 3274+00	LT	-	-	-	6	-
STA 3260+00	STA 3274+00	RT	-	-	-	-	-
STA 3288+00	RENWICK ROAD	LT	-	-	-	6	-
STA 3288+00	RENWICK ROAD	RT	-	-	-	-	-
RENWICK ROAD	FORT BEGGS DRIVE	LT	-	-	-	12	-
RENWICK ROAD	ROBERTS AVENUE	RT	-	-	-	-	-
FORT BEGGS DRIVE	UNION STREET	LT	-	-	-	7	-
STAGE 4 SUBTOTAL			0	0	0	31	0

EROSION CONTROL QUANTITY SCHEDULE SUMMARY

	25100630	28000250	28000300	28000510	X0323973
STAGE	EROSION CONTROL BLANKET (SY)	TEMPORARY EROSION CONTROL SEEDING (LB)	TEMPORARY DITCH CHECKS (EACH)	INLET FILTERS (EACH)	SEDIMENT CONTROL, SILT FENCE
PRESTAGE SUBTOTAL	71864	1492	44	65	12166
STAGE 1 SUBTOTAL	43463	902	11	113	6680
STAGE 2 SUBTOTAL	39724	826	0	131	371
STAGE 3 SUBTOTAL	0	0	0	0	0
STAGE 4 SUBTOTAL	0	0	0	31	0
PROJECT TOTAL	155051	3220	55	340	19217

EROSION CONTROL BLANKET
SUBTOTAL FOR TEMPORARY SEEDING

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG
**EROSION CONTROL
SCHEDULE OF QUANTITIES**