

CONTRACT NO. 62417

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(113 & 114) R-5	WILL	525	58
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FAP 338 (IL RTE. 59)	

TEMPORARY DRAINAGE SCHEDULE			5421C012	5421C024	5421C030	X0321193	X0323236		X0322938
STATION OR BEGINNING DESCRIPTION	STATION OR ENDING DESCRIPTION	OFFSET (LT/RT)	PIPE CULVERTS, CLASS C, TYPE 1, 12" (TEMPORARY) (FT)	PIPE CULVERTS, CLASS C, TYPE 1, 24" (TEMPORARY) (FT)	PIPE CULVERTS, CLASS C, TYPE 1, 30" (TEMPORARY) (FT)	TEMPORARY CATCH BASINS (EACH)	TEMPORARY INLET (EACH)	TEMPORARY MANHOLE (EACH)	TEMPORARY END SECTION (EACH)
PRE-STAGE									
BRIDGE	DAYFIELD DR.	LT	53	-	-	5	-	-	-
ROLF ROAD	DAYFIELD DR. (FUTURE)	RT	30	-	-	-	-	-	-
DAYFIELD DR.	WEDGEWOOD CT.	LT	6	-	-	-	-	-	1
WEDGEWOOD CT.	FRASER / FEENEY ROAD	LT	7	-	25	1	-	-	1
FRASER / FEENEY ROAD	RENWICK ROAD	RT	82	-	-	1	-	1	3
RENWICK ROAD	ROBERTS AVE	RT	127	16	-	3	-	-	-
FORT BEGGS DR.	UNION ST.	LT	-	-	-	-	-	-	-
ROBERTS AVE.	UNION ST.	RT	260	-	-	2	2	-	-
UNION ST.	STA 3330+80	RT	-	-	-	-	-	-	-
PRE-STAGE SUBTOTAL			565	16	25	12	2	1	5
STAGE 1									
STA 3193+25	BRIDGE	LT	15	-	-	-	-	-	-
RENWICK ROAD	FORT BEGGS DR.	LT	43	-	-	-	-	-	-
FORT BEGGS DR.	UNION ST.	LT	13	-	-	-	-	-	-
STAGE 1 SUBTOTAL			71	0	0	0	0	0	0
PROJECT TOTAL			636	16	25	12	2	1	5

ILLINOIS DEPARTMENT OF TRANSPORTATION
 DISTRICT NO. 1 SCHAUMBURG
 TEMPORARY DRAINAGE
 SCHEDULE OF QUANTITIES

SCALE NONE
 DATE MARCH 18, 2008
 DRAWN BY TB
 CHECKED BY JCM