

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE URBAN 1000-1A	100% STATE TRAFFIC Y031-1F	OPTICOM CITY OF ELGIN TRAFFIC Y031-3D	100% STATE LIGHTING Y030-1E	100% CITY OF ELGIN LIGHTING Y030-1E
* X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	50	50				
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2670		2670			
X0323503	STORM SEWERS, TYPE 2 WYE 21" PIPE - 12" BRANCH	EACH	18				18	
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18				18	
* X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	12				12	
* X0325705	REOPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1		1			
* X0325742	CONCRETE FOUNDATION, TYPE E (SPECIAL)	FOOT	15		15			
X0325751	DRIVING SOLDIER PILES	FOOT	7126	7126				
X0325775	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	39631	39631				
X0325837	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	1734	1734				
X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	411	411				
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	235	235				
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	618	618				
* X0325860	TEMPORARY WOOD POLE, 60 FT., CLASS 4, WITH 15 FT. MAST ARM, INSTALL ONLY	EACH	19				19	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5				
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	1354	1354				
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	2157	2157				
* X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	1				1	
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1			
* X8101280	CONDUIT IN TRENCH, 3" DIA., RIGID GALVANIZED STEEL	FOOT	500				500	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE URBAN 1000-1A	100% STATE TRAFFIC Y031-1F	OPTICOM CITY OF ELGIN TRAFFIC Y031-3D	100% STATE LIGHTING Y030-1E	100% CITY OF ELGIN LIGHTING Y030-1E
* X8102010	CONDUIT PUSHED, 3" DIA., RIGID GALVANIZED STEEL	FOOT	500				500	
* X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING	EACH	10				10	
* X8410113	REMOVE TEMPORARY LIGHTING UNITS AND SALVAGE	EACH	30				30	
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1			
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2694		2694			
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1675		1675			
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2353			2353		
XX004104	PRE-EMERGENT GRANULAR HERBICIDE	POUND	50	50				
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	33				33	
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1			
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	19921	19921				
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1				
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4				
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2				

\* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
US 20 @ SHALES PARKWAY

PLOT DATE: 2/20/2008

P:\000008\cafract\cafract\137038\cafract\st0006.dgn