



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2008

SUBJECT: FAI Route 90/94
Section 2324.6 -1P- I-4
Cook County
Contract No. 62999
Item No. 5P, June 13, 2008 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 & 2 of the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised pages 3 – 6 of the Special Provisions.
4. Added page 35 to the Special Provisions.
5. Revised sheets 3, 4, 10, 11 & 13 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62999

State Job # - C-91-257-05
 PPS NBR - 1-74823-1631
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2324.6-1P-I-4

Project Number

Route
 FAI 90/94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322256	TEMP INFO SIGNING	SQ FT	26.000				
X0323973	SED CONT SILT FENCE	FOOT	624.000				
X0323974	SED CONT SILT FN MAIN	FOOT	156.000				
* X0324640	FLUTED KNEEWALL	FOOT	409.000				
* X0325891	IMP ATTEN FRD RES TL2	EACH	1.000				
* DELETED							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
* DELETED							
20200100	EARTH EXCAVATION	CU YD	132.000				
21101645	TOPSOIL F & P 12	SQ YD	132.000				
25000210	SEEDING CL 2A	ACRE	0.080				
25000400	NITROGEN FERT NUTR	POUND	8.000				
25000500	PHOSPHORUS FERT NUTR	POUND	8.000				
25000600	POTASSIUM FERT NUTR	POUND	8.000				
* DELETED							
25100630	EROSION CONTR BLANKET	SQ YD	364.000				

* REVISED : JUNE 4, 2008

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62999

State Job # - C-91-257-05
 PPS NBR - 1-74823-1631
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2324.6-1P-I-4

Project Number

Route
 FAI 90/94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42001300	PROTECTIVE COAT	SQ YD	27.000				
44002300	CURB REMOVAL PART	FOOT	59.000				
44004250	PAVED SHLD REMOVAL	SQ YD	49.000				
* DELETED							
* DELETED							
* DELETED							
* DELETED							
* DELETED							
60618324	CONC MEDIAN SURF 6 SP	SQ FT	188.000				
66400550	CH LK FENCE 4 SPL	FOOT	580.000				
67100100	MOBILIZATION	L SUM	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	6.000				
			* REVISED : JUNE 4, 2008				

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS	1
COMPLETION DATE PLUS GUARANTEED WORKING DAYS.....	2
COORDINATION WITH ADJACENT AND/OR OVERLAPPING CONTRACTS	2
CONTRACTOR COOPERATION	3
TRAFFIC CONTROL AND PROTECTION (SPECIAL)	3
TRAFFIC CONTROL PLAN	5
ADVANCED PUBLIC NOTIFICATION.....	6
TEMPORARY INFORMATION SIGNING	6
CONTRACTOR'S DAILY WORK SCHEDULE	7
TRAFFIC CONTROL FOR WORK ZONE AREAS	8
SEEDING, CLASS 2A.....	8
EROSION CONTROL BLANKET	9
CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	9
CHAIN LINK FENCE, 4' (SPECIAL)	11
FLUTED KNEE WALL.....	11
RUSTICATION FINISH FOR FLUTED KNEE WALLS	12
CURB REMOVAL (PARTIAL).....	13
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE)	13
CEMENT (BDE)	16
EQUIPMENT RENTAL RATES (BDE).....	19
EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)	20
IMPACT ATTENUATORS (BDE).....	20
PAYMENTS TO SUBCONTRACTORS (BDE)	21
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE)	22
REINFORCEMENT BARS (BDE)	23
SEEDING (BDE)	24
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE).....	25
SILT FILTER FENCE (BDE)	29
STEEL PLATE BEAM GUARDRAIL (BDE)	30
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	30
TEMPORARY EROSION CONTROL (BDE)	30
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	31
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC	35

Revised 06/05/2008

CONTRACTOR COOPERATION

The Contractor's attention is directed to the fact that other separate contracts may be under construction during the duration of this Contract and that the Contractor will be governed by Article 105.08 of the Standard Specifications.

The Contractor will coordinate proposed project start dates and sequence of construction with the Engineer and other Contractors to present an effective and timely schedule for successful completion of the project.

No additional compensation will be allowed the Contractor for the above requirements or for any delays or inconvenience resulting from the activities of other contractors.

TRAFFIC CONTROL AND PROTECTION (SPECIAL)

This item of work shall include furnishing, installing, maintaining, replacing, relocating and removing all traffic control devices used for the purpose of regulating, warning or directing traffic during the construction or maintenance of this improvement.

Traffic Control and Protection shall be provided as called for in the plans, these Special Provisions, applicable Highway Standards, applicable sections of the Standard Specifications, or as directed by the Engineer.

The governing factor in the execution and staging of work for this project is to provide the motoring public with the safest possible travel conditions along the roadway through the construction zone. The Contractor shall arrange his operations to keep the closing of any lane of the roadway to a minimum.

Traffic Control Devices include signs and their supports, signals, pavement markings, barricades with sand bags, channelizing devices, warning lights, arrow boards, flaggers, or any other device used for the purpose of regulating, detouring, warning or guiding traffic through or around the construction zone.

The Contractor is required to conduct routine inspections of the worksite at a frequency that will allow for the prompt replacement of any traffic control device that has become displaced, worn or damaged to the extent that it no longer conforms to the shape, dimensions, color and operational requirements of the MUTCD, the Traffic Control Standards or will no longer present a neat appearance to motorists. A sufficient quantity of replacement devices, based on vulnerability to damage, shall be readily available to meet this requirement.

The Contractor shall be responsible for the proper location, installation and arrangement of all traffic control devices. Special attention shall be given to advance warning signs during construction operations in order to keep lane assignment consistent with barricade placement at all times. The Contractor shall immediately remove, cover or turn from the view of the motorists all traffic control devices which are inconsistent with detour or lane assignment patterns and conflicting conditions during the transition from one construction stage to another. When the Contractor elects to cover conflicting or inappropriate signing, materials used shall totally block out reflectivity of the sign and shall cover the entire sign. The method used for covering the signing shall meet with the approval of the Engineer.

Revised 06/05/2008

The Contractor shall coordinate all traffic control work on this project with adjoining or overlapping projects, including barricade placement necessary to provide a uniform traffic detour pattern. When directed by the Engineer, the Contractor shall remove all traffic control devices, which were furnished, installed and maintained by him under this contract, and such devices shall remain the property of the Contractor. All traffic control devices shall remain in place until specific authorization for relocation or removal is received from the Engineer.

The Contractor shall ensure that all traffic control devices installed by him are operational, functional and effective 24 hours a day, including Sundays and holidays.

Signs. All signs, except those referring to daily lane closures, shall be post mounted in accordance with Standard 701901 for all projects that exceed four days.

Prior to the beginning of construction operations, the Contractor will be provided a sign log of all existing signs within the limits of the construction zone. The Contractor is responsible for verifying the accuracy of the sign log. Throughout the duration of this project, all existing traffic signs shall be maintained by the Contractor. All provisions of Article 107.25 of the Standard Specifications shall apply, except the third paragraph shall be revised to read: "The Contractor shall maintain, furnish and replace at his own expense, any traffic sign or post which has been damaged or lost by the Contractor or a third party."

Whenever any vehicle, equipment, workers or their activities infringe on the shoulder or within 4.5 m (15 feet) of the traveled way and the traveled way remains unobstructed, then the applicable Traffic Control Standard shall be 701006. "Shoulder Work Ahead" sign (W21-5(0)-48) shall be used in lieu of the "Workers" sign (W21-1 or W21-1a).

Barricades. Any drop off greater than 75 mm (3 inches), within 2.5 m (8 feet) of the pavement edge shall be protected by Type I or II barricades equipped with mono-directional steady burn lights at 8 m (25 feet) center to center spacing. Barricades that are placed in excavated areas shall have leg extensions installed such that the top of the barricade is in compliance with the height requirements of Standard 701901.

All Type I and Type II barricades, drums, and vertical panels shall be equipped with a steady burn light when used during hours of darkness unless otherwise stated herein.

Check barricades shall be placed in work areas perpendicular to traffic every 300 m (1,000 feet), one per lane and per shoulder, to prevent motorists from using work areas as a traveled way. Two additional check barricades shall be placed in advance of each patch excavation or any hazard in the work area, the first at the edge of the open traffic lane and the second centered in the closed lane. Check barricades shall be Type I or II and equipped with a flashing light.

Public Convenience and Safety. At the preconstruction meeting, the Contractor shall furnish the name of the individual in his direct employ who is to be responsible for the installation and maintenance of the Traffic Control for this project. The Contractor shall also provide a telephone number where a responsible individual can be contacted on a 24-hour-a-day basis to receive notification of any deficiencies regarding traffic control and protection. The Contractor shall dispatch men, materials and equipment to correct any such deficiencies. The Contractor

Revised 06/05/2008

shall respond to any call from the Department concerning any request for improving or correcting traffic control devices and begin making the requested repairs within two hours from the time of notification.

Personal vehicles shall not park within the right-of-way except in specific areas designated by the Engineer.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at the locations approved by the Engineer.

No road closure, lane closures or restriction shall be permitted without prior approval by the Engineer.

All daily lane closures shall be removed during adverse weather conditions such as rain, snow, and/or fog and as determined by the Engineer.

Additional lane closure hour restrictions may have to be imposed to facilitate the flow of traffic to and from major sporting events and/or other events.

Method of Measurement. This item of work will be measured on a lump sum basis for furnishing, installing, maintaining, replacing, relocating and removing the traffic control devices required in the plans, specifications and these Special Provisions.

Basis of Payment. This work will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL), which price shall be payment in full for all labor, materials, transportation, handling and incidentals necessary to furnish, install, maintain, replace, relocate and remove all traffic control devices indicated in the plans, specifications and these Special Provisions. The salvage value of the materials removed shall be reflected in the bid price for this item.

Delays to the Contractor caused by complying with these requirements will be considered incidental to the item for Traffic Control and Protection, and no additional compensation will be allowed.

(BBA – 02/13/2008)

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: October 1, 1995

Traffic Control shall be in accordance with the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

Revised 06/05/2008

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

HIGHWAY STANDARDS

- 701601 Urban Lane Closure, Multilane, 1w or 2w With Nontraversable Median
- 701701 Urban Lane Closure, Multilane Intersection
- 701801 Lane Closure Multilane 1w or 2w Crosswalk or Sidewalk Closure
- 701901 Traffic Control Devices

PLANS AND DETAILS

- TC-10 District 1, Traffic Control And Protection For Side Roads, Intersections And Driveways
- TC-17 District 1, Traffic Control Details For Freeway Shoulder Closures And Partial Ramp Closures
- TC-18 District 1, Signing For Flagging Operations At Work Zone Openings

RECURRING SPECIAL PROVISIONS AND SPECIAL PROVISIONS

- Advanced Public Notification
- Keeping the Expressway Open to Traffic
- Traffic Control and Protection (Special)
- Traffic Control for Work Zone Areas
- Reflective Sheeting on Channelizing Devices

ADVANCED PUBLIC NOTIFICATION

The Contractor shall provide notice to the public a minimum of 14 days in advance of any work that requires the closure of lanes through the use of a changeable message sign or temporary information signing.

TEMPORARY INFORMATION SIGNING

Description. This item consists of furnishing, installing, maintaining, relocating for various states of construction and eventually removing temporary informational signs. Included in this item may be ground mount signs, skid mount signs, truss mount signs, bridge mount signs, and overlay sign panels which cover portions of existing signs.

Materials: Materials shall be according to the following Articles of Section 1000 - Materials:

	<u>Item</u>	<u>Article/Section</u>
a)	Sign Base (Notes 1 & 2)	1090
b)	Sign Face (Note 3)	1091
c)	Sign Legends	1092
d)	Sign Supports	1093
e)	Overlay Panels (Note 4)	1090.01

Revised 06/05/2008

KEEPING THE EXPRESSWAY OPEN TO TRAFFIC

Whenever work is in progress on or adjacent to an expressway, the Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required in these Special Provisions, the Standard Specifications, the State Standards and the District Freeway details. All Contractors' personnel shall be limited to these barricaded work zones and shall not cross the expressway.

The Contractor shall request and gain approval from the Illinois Department of Transportation's Expressway Traffic Operations Engineer (847-705-4151) twenty-four (24) hours in advance of all daily lane, ramp and shoulder closures and seventy-two (72) hours in advance of all permanent and weekend closures on all Freeways and/or Expressways in District One. This advance notification is calculated based on workweek of Monday through Friday and shall not include weekends or Holidays.

LOCATION: I-90/94 DAN RYAN (29th to 95th)

WEEK NIGHT	TYPE OF CLOSURE	ALLOWABLE LANE CLOSURE HOURS					
		INBOUND		OUTBOUND			
Sunday thru Thursday	Temporary Partial	8:00PM	-	5:00 AM	9:00PM	-	6:00 AM
Friday	Ramp & Shoulder	8:00PM (Fri)	-	6:00 AM (Sat)	9:00PM (Fri)	-	7:00 AM (Sat)
Saturday	Closures	8:00PM (Sat)	-	Noon (Sun)	9:00PM (Sat)	-	Noon (Sun)

In addition to the hours noted above, temporary partial ramp and temporary shoulder closures will be allowed weekdays between the hours of 9:00 AM and 3:00 PM.

Narrow lanes and permanent shoulder closures will not be allowed between December 1st and April 1st.

All daily closures shall be removed during adverse weather conditions such as rain, snow, and/or fog and as determined by the Engineer.

Additional hour restrictions may have to be imposed to facilitate the flow of traffic to and from major sporting events and/or other events.

All closure signs shall not be erected any earlier than one-half (1/2) hour before the starting hours listed above. Also, these signs should be taken down within one-half (1/2) hour after the closure is removed.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at the locations approved by the Engineer.

(District 1 11/16/06)

Added 06/05/2008