

P. A. SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00148-00-TL	COOK	273	015
STA.		TO STA.		
FED. ROAD DIST. NO.		ALANCE	FED. AID PROJECT	

CONTRACT NO. 63003

CODED PAY ITEM	PAY ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE Y031-1F																									
			CITY OF CHICAGO HEIGHTS												CITY OF COUNTRY CLUB HILLS					VILLAGE OF GLENWOOD					VILLAGE OF HAZEL CREST			
			Rt. 30 & Division Street	Rt. 30 & Chicago Road	Rt. 30 & Halsted Street	Rt. 30 & S State Street	Joe Orr & Chicago Road	Joe Orr & Halsted Street	Halsted & Vollmer Road	Chicago Road & 16th Street	Cicero Avenue & Flossmoor Road	Cicero Avenue & 83rd Street	Cicero Avenue & 175th Street	Pulaski (Crawford) & 167th Street	Main & North Main	Glenwood Lansing & Glenwood Dyer Road	Cottage Grove & Glenwood Dyer Road	Main Street & Young	167th Street & Glenwood-Chicago Heights Road	167th Street & Head Avenue	South Suburban Hospital & Kedzie Avenue	175th Street & Kedzie Avenue	183rd Street & Kedzie Avenue	183rd Street & Grenoble Avenue	175th Street & Governors Highway			
	INTERSECTION NUMBER -->		41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT																										
44000600	SIDEWALK REMOVAL	SQ FT																	100									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO																										
67100100	MOBILIZATION	L SUM																										
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM																										
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT																	5									
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT																										
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH																										
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH																										
85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH												1														
85700505	FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH																										
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	274	276	456	224	736	313	315	454	304	311	376	338	348	366	425	580	297	320	265	250	300	210	300			
87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT																										
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH													1				2									
87800100	CONCRETE FOUNDATION, TYPE A	FOOT																	4									
87900200	DRILL EXISTING HANDHOLE	EACH																	1									
88900100	INDUCTIVE LOOP DETECTOR	EACH																										
88700200	LIGHT DETECTOR	EACH	2	2	2	2	3	2	2	2	2	2	2	2	2	2	3	3	2	2	2	3	3	3	3			
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1			
89900100	RELOCATE EXISTING SIGNAL HEAD	EACH													2				3									
89900200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH																										
89900400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH																										
89902200	MODIFY EXISTING CONTROLLER	EACH												1														
89902300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT																										
89902350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT																			265		300	210	300			
89902375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH													30				45									
X0301023	CONFIRMATION BEACON	EACH													1	1						1		1	1			
X0322131	EMERGENCY VEHICLE PREEMPTION PUSH BUTTON ASSEMBLY	EACH																										
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	274	276	456	224	736	313	315	454	304	311	376	338	348	366	425	580	575	320	265	250	300	210	300			
X8730350	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT																										
X8780110	MODIFY EXISTING TYPE "D" FOUNDATION	EACH																										
XY027226	MAGNETIC DETECTOR AMPLIFIER	EACH																										
Z0076600	TRAINEES	HOURL	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8	3.8			

* PLANS MODIFIED BY
ROBINSON ENGINEERING, LTD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**PROPOSED EMERGENCY VEHICLE PREEMPTION
SUMMARY OF QUANTITIES**

SCALE: VERT.
HORIZ.
DATE 01/02/08

DRAWN BY
CHECKED BY