


## CONTRACT NO. 63003



## **EMERGENCY VEHICLE PREEMPTION SEQUENCE**

DUAL ENTRY PHASE SINGLE ENTRY PHASE

NUMBER REFERS TO ASSOCIATED PHASE

PROPOSED EMERGENCY VEHICLE	PREEMPTO	ORS
EMERGENCY VEHICLE PREEMPTOR	3	4
MOVEMENT	<b>←</b>	<b>↓</b> ↑

SCHEDULE OF QUANTITIES				
PAY ITEM	UNIT	QUANTITY		
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	286		
LIGHT DETECTOR	EACH	2		
LIGHT DETECTOR AMPLIFIER	EACH	1		
ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	286		

★ 1. THIS PLAN IS FOR THE PURPOSE OF INSTALLING EMERGENCY VEHICLE PREEMPTION EQUIPMENT AS SHOWN PER PLAN INDICATED IN THE SCHEDULE OF QUANTITIES. ALL OTHER EQUIPMENT SHOWN SHALL BE DISREGARDED.

## VILLAGE OF HOMEWOOD **LOCATION NO. 82**

ILLINOIS DEPARTMENT OF TRANSPORTATION \* PLANS MODIFIED BY ROBINSON ENGINEERING, LTD PROPOSED EMERGENCY VEHICLE PREEMPTION CABLE PLAN, PHASE DESIGNATION DIAGRAM & SCHEDULE OF QUANTITIES ADDED EV PREEMPTION 01/02/08 175TH STREET & ASHLAND AVENUE SCALE: VERT. HORIZ. CHECKED BY