

SCHEDULE OF PAVEMENT PATCHING				
CLASS B PATCHES, TYPE II, 9"				
START	END	WIDTH	O/S	AREA SQYD
92+00	92+10	10'	5' R	11.1
99+50	99+60	10'	5' R	11.1
TOTAL				22.2

SCHEDULE OF PAVEMENT PATCHING				
CLASS B PATCHES, TYPE III, 9"				
START	END	WIDTH	O/S	AREA SQYD
93+00	93+06	26'	26' L	17.3
96+54	96+62	26'	26' R	23.1
96+50	96+58	26'	26' L	21.3
98+00	98+06	26'	26' L	17.3
100+00	100+06	26'	26' R	17.3
104+00	104+06	26'	26' R	17.3
109+00	109+06	26'	26' L	17.3
TOTAL				130.9

SCHEDULE OF PAVEMENT PATCHING				
CLASS B PATCHES, TYPE IV, 9"				
START	END	WIDTH	O/S	AREA SQYD
82+50	82+90	79.0'	39.5' R	351.1
83+40	83+80	79.0'	39.5' R	351.1
84+20	84+60	79.0'	39.5' R	351.1
85+00	85+20	79.0'	39.5' R	175.6
TOTAL				1,228.9

PAVEMENT STRIPING TABLE	
ITEM DESCRIPTION	SYMBOL
THERMOPLASTIC PAVEMENT MARKING, LINE 4", 30' SKIP 10' DASH, WHITE	A
THERMOPLASTIC PAVEMENT MARKING, LINE 4", DOUBLE @ 11' C-C YELLOW	B
THERMOPLASTIC PAVEMENT MARKING, LINE 6", TURN LANE WHITE	C
THERMOPLASTIC PAVEMENT MARKING, LINE 6" PEDESTRIAN CROSSWALK, WHITE	D
THERMOPLASTIC PAVEMENT MARKING, LINE 8", ISLAND EDGING, WHITE	E
THERMOPLASTIC PAVEMENT MARKING, LINE 12", SCHOOL CROSSWALK @ 36" C-C, WHITE	F
THERMOPLASTIC PAVEMENT MARKING, LINE 12", MEDIAN DIAGONALS @ 45 DEGREES, YELLOW	G
THERMOPLASTIC PAVEMENT MARKING, LINE 24", STOP BAR, WHITE	H
THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS	I

REVISION:

**OAK LAWN  
SOUTHWEST HIGHWAY LAPP PROJECT  
SCHEDULES & TABLES**

SCALE: NONE

DRAWN BY: DMM  
CHECKED BY: BP  
DATE: 1/4/2008

**HANCOCK ENGINEERING** ♦ Civil Engineers ♦ Municipal Consultants ♦ Established 1911

9933 Roosevelt Road  
Westchester, Illinois 60154-2780  
Phone: 708/865-0300  
Fax: 708/865-1212

Drawing file: W:\Projects\64036092 - Southwest Highway LAPP\TABLES.dwg Jan 17, 2008 - 8:50am