

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	70% FED. - 30% VILLAGE		100% VILLAGE	
				1000		UTIL.	ROAD.
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5			
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2			
60261320	INLETS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	3	3			
+ 60266500	VALVE VAULTS TO BE REMOVED	EACH	1			1	
+ 60266800	VALVE BOXES TO BE REPLACED	EACH	2			2	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2916	2916			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
• 72000100	SIGN PANEL - TYPE 1	SQ FT	181	181			
• 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10			
• 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	96	96			
• 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	514	514			
• 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	20	20			
• 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	816	816			
• 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	104	104			
• 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	130	130			
• 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	180	180			
• 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	67	67			
A2004820	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9	9			
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	108	108			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	515	515			
X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	50	50			
+ X0323449	REMOVE EXISTING WATER VALVE	EACH	3			3	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	38	38			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1			
+ XX002029	SANITARY SEWER REMOVAL, 8"	FOOT	128			128	
+ XX003673	SANITARY SERVICE REPLACEMENT	EACH	5			5	
XX005656	INLET FILTER CLEANING	EACH	108	108			
XX006120	ABANDON STORM SEWER	FOOT	108	108			
XX006645	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 3, 18"	FOOT	52	52			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0017190	DOWEL BARS 1"	EACH	540	540			
+ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15			15	
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	11	11			
+ Z0056900	SANITARY SEWER 8"	FOOT	128			128	
Z0075310	TIE BARS 3/4"	EACH	410	410			
Z0076600	TRAINEES	HOUR	500	500			

• SPECIALTY ITEMS

+ NON-PARTICIPATING