

F. A. U. SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3596	06-00031-00-LS	COOK	5	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT # 63025

SUMMARY OF QUANTITIES						
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE	
					PAVEMENT	LANDSCAPE
					1000	Y003
	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	180	180	
	44000600	SIDEWALK REMOVAL	SQ FT	180	180	
	44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	40	40	
	60600605	CONCRETE CURB, TYPE B	FOOT	270	270	
	67100100	MOBILIZATION	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
*	A2008120	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	18		18
*	K1003680	MULCH	SQ YD	30		30
	X0322484	CURB CUT	FOOT	168	168	
*	XX007307	HMA PAVEMENT TEXTURING	SQ FT	976	976	
	XX007368	COAL TAR SEAL COAT WITH CRACK FILLER	SQ FT	5850	5850	
	XX007369	HOT MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT, 8"	SQ YD	156	156	
	XX007370	PARKWAY REMOVAL AND REPLACEMENT, 3"	SQ FT	1015	1015	

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES
SCENIC BEAUTIFICATION
AT STATE STREET
FROM YATES TO HOXIE AVENUE**

SCALE: VERT. _____ DRAWN BY JZ
 HORIZ. NONE CHECKED BY DWS
 DATE 12-14-07

ROBINSON ENGINEERING, L.T.D.
 1700 SOUTH PARK AVENUE, SOUTH HOLLAND, ILLINOIS 60473
 PHONE 312-430-0000 FAX 312-430-0005
 ILLINOIS DESIGN PER 1 REGISTRATION NO. 148001128 06/179-CJIAN-01-P01