

| | | | | |
|---------------------|----------------|------------------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 2678 | 08-00169-00-LT | DUPAGE | 39 | 2 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |
| CONTRACT NO. 63027 | | | | |

GENERAL NOTES:

- ACCESS TO LOCAL RESIDENCES AND BUSINESSES SHALL BE MAINTAINED DURING CONSTRUCTION.
- THE CONTRACTOR SHALL GIVE THE MUNICIPALITY AND JAMES J. BENES AND ASSOCIATES, INC. THREE (3) WORKING DAYS NOTICE PRIOR TO THE COMMENCEMENT OF WORK.
(JAMES J. BENES AND ASSOCIATES, INC.: (630) 719-7570)
(CITY OF ELMHURST : (630) 530-3000)
- ALL ELEVATIONS ARE ON U.S.G.S. DATUM.
- DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- NEITHER THE ENGINEER, NOR THE OWNER, SHALL ASSUME ANY OF THE RESPONSIBILITIES OF THE CONTRACTOR'S SUPERINTENDENT OR OF SUBCONTRACTORS. ADDITIONALLY, NEITHER THE ENGINEER, NOR THE OWNER, SHALL ADVISE ON, OR ISSUE DIRECTIONS CONCERNING, ASPECTS OF CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, OR SAFETY PRECAUTIONS AND/OR PROGRAMS IN CONNECTION WITH THE WORK.
- THE LOCATIONS OF PUBLIC OR PRIVATE UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND THEIR ACCURACY IS NOT GUARANTEED. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION AND ELEVATION OF ALL UTILITIES. THE CONTRACTOR SHALL REPORT ANY ENCOUNTERED DISCREPANCIES TO THE ENGINEER AT ONCE. THE CONTRACTOR SHALL TAKE DUE CARE IN ALL PHASES OF CONSTRUCTION TO PROTECT ANY UTILITIES WHICH MAY BE AFFECTED BY THE WORK. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. CONTACT JULIE 48 HOURS PRIOR TO DIGGING (JULIE: 1-800-892-0123)
- THE CONTRACTOR SHALL KEEP THE CONSTRUCTION AREA FREE OF DEBRIS AND/OR OBJECTIONABLE MATERIALS DURING CONSTRUCTION. THE CONTRACTOR SHALL INSPECT THE SITE DAILY FOR DEBRIS ON THE ROADWAY SURFACE. THE RIGHT-OF-WAY SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITION.
- THE CONTRACTOR SHALL MAINTAIN ALL EXISTING DRAINAGE FACILITIES DURING CONSTRUCTION AND SHALL REPAIR ANY DRAINAGE FACILITIES DAMAGED DURING CONSTRUCTION. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND WILL NOT BE PAID FOR SEPARATELY.
- THE RELOCATION OF SIGNS ARE INCIDENTAL TO THE CONTRACT.
- CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF ELMHURST.
- ALL UNIT PAVERS AND UNIT PAVERS, TACTILE SHALL BE INSTALLED ON P.C.C. CONCRETE UNDERLAYMENTS, UNLESS OTHERWISE SPECIFIED. SIDEWALK RAMPS MUST FOLLOW DETECTABLE WARNING GUIDELINES.
- ALL SIDEWALK RAMPS SHALL FOLLOW DETECTABLE WARNING GUIDELINES AND SHALL BE INSTALLED AS PER THE DETAIL FOR UNIT PAVERS, TACTILE.
- IN SIDEWALK AREAS, P.C.C. UNDERLAYMENT SHALL BE 4 INCHES THICK.
- DRIVEWAY DIMENSIONS ARE NOT INDICATED AND GENERALLY CONFORM TO EXISTING WIDTHS OF DRIVEWAY OPENINGS. CONTRACTOR SHALL CONFIRM FINAL WIDTHS WITH OWNER'S REPRESENTATIVE PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- NEW SIDEWALKS SHALL BE CONSTRUCTED TO PROVIDE POSITIVE DRAINAGE AWAY FROM STRUCTURES.
- EXISTING TRAFFIC SIGNAL HARDWARE SHALL REMAIN.
- CONTRACTOR SHALL REMOVE PAVEMENT TO LIMITS INDICATED ON DRAWINGS.
- CONTRACTOR SHALL PROTECT ALL EXISTING ELEMENTS TO REMAIN, INCLUDING TREES, FENCES, AND WALLS.
- SOD PARKWAY SHALL BE 3'-0" WIDE UNLESS OTHERWISE NOTED.

IDOT STANDARDS:

| | |
|-----------|--|
| 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 424001-05 | CURB RAMPS FOR SIDEWALKS |
| 442201-03 | CLASS C AND D PATCHES |
| 604001-02 | FRAME AND LIDS TYPE 1 |
| 604006-03 | FRAME AND GRATE TYPE 3 |
| 604011-03 | FRAME AND GRATE TYPE 3V |
| 604086-01 | FRAME AND GRATE TYPE 23 |
| 606001-03 | CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER |
| 701501-04 | URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED |
| 701801-03 | LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE |
| 701901 | TRAFFIC CONTROL DEVICES |
| 805001 | ELECTRIC SERVICE INSTALLATION DETAILS |
| 814001-01 | CONCRETE HANDHOLES |

INDEX OF SHEETS:

| SHEET | |
|-------|--|
| 1 | TITLE SHEET |
| 2 | INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES |
| 3 | SUMMARY OF QUANTITIES |
| 4 | TYPICAL SECTIONS AND BENCHMARKS |
| 5-7 | STREETSCAPE PLAN SHEETS |
| 8-10 | LIGHTING PLAN SHEETS |
| 11 | CONSTRUCTION DETAILS |
| 12-15 | LIGHTING DETAILS |
| 16 | TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS |
| 17 | CITY CENTRE - COVER |
| 18 | CITY CENTRE - DEMOLITION PLAN |
| 19 | CITY CENTRE - HARDSCAPE PLAN |
| 20 | CITY CENTRE - DIMENSION PLAN |
| 21 | CITY CENTRE - LANDSCAPE PLAN |
| 22 | CITY CENTRE - PAVING DETAILS |
| 23 | CITY CENTRE - WALL AND SIGN DETAILS |
| 24 | CITY CENTRE - FOUNTAIN PLAN AND SECTIONS |
| 25 | CITY CENTRE - MISCELLANEOUS DETAILS |
| 26 | CITY CENTRE - SITE FURNITURE/GENERAL NOTES |
| 27 | CITY CENTRE - LANDSCAPE DETAILS AND NOTES |
| 28 | CITY CENTRE - FOUNTAIN DETAILS |
| 29 | POLICE PLAZA - COVER |
| 30 | POLICE PLAZA - DEMOLITION PLAN |
| 31 | POLICE PLAZA - HARDSCAPE PLAN |
| 32 | POLICE PLAZA - DIMENSION PLAN |
| 33 | POLICE PLAZA - LANDSCAPE PLAN |
| 34 | POLICE PLAZA - PLANTER/SEATWALL DETAILS |
| 35-36 | POLICE PLAZA - HARDSCAPE DETAILS |
| 37 | POLICE PLAZA - SITE FURNITURE/GENERAL DETAILS |
| 38 | POLICE PLAZA - PLANTING DETAILS |
| 39 | POLICE PLAZA - PLANTING NOTES |

| REVISIONS | |
|---------------|---------|
| NAME | DATE |
| IDOT COMMENTS | 3/27/07 |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U.
YORK ROAD

INDEX OF SHEETS,
STATE STANDARDS
AND GENERAL NOTES

SCALE: NTS
DATE: 12/22/07

DRAWN BY: BCD
CHECKED BY: JDS