

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	08-00169-00-LT	DUPAGE	39	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63027				

SUMMARY OF QUANTITIES					
ITEM CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	Y003	Y030-1E
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	66	66	
20101000	TEMPORARY FENCE	FOOT	630	630	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	659.8	659.8	
*25200200	SUPPLEMENTAL WATERING	UNIT	2	2	
*25200700	SODDING, SPECIAL	SQ YD	187	187	
*25301500	TREES	EACH	6	6	
*25301700	SHRUBS	EACH	66	66	
*25400100	PERENNIAL PLANTS	UNIT	40	40	
42001300	PROTECTIVE COAT	SQ YD	1,033	1,033	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	180	180	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	375	375	
44000100	PAVEMENT REMOVAL	SQ YD	883	883	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	180	180	
44000300	CURB REMOVAL	FOOT	136	136	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,512	2,512	
44000600	SIDEWALK REMOVAL	SQ FT	23,763	23,763	
*56200300	WATER SERVICE LINE, 1"	FOOT	150	150	
*56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	29	29	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	12	12	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	11	11	
60404300	FRAMES AND GRATES, TYPE 3	EACH	4	4	
60404305	FRAMES AND GRATES, TYPE 3V	EACH	6	6	
60404940	FRAMES AND GRATES, TYPE 23	EACH	2	2	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4	4	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	7	7	
60600605	CONCRETE CURB, TYPE B	FOOT	132	132	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,349	2,349	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	163	163	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
*80400100	ELECTRIC SERVICE INSTALLATION	EACH	2		2
*80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1
*81000600	CONDUIT IN TRENCH, 2" DIA, GALVANIZED STEEL	FOOT	291		291
*81012500	CONDUIT IN TRENCH, 1 1/2" DIA, PVC	FOOT	5,250		5,250
*81018500	CONDUIT, PUSHED, 2" DIA, GALVANIZED STEEL	FOOT	250		250
*81018900	CONDUIT, PUSHED, 4" DIA, GALVANIZED STEEL	FOOT	112		112
*81400100	HANDHOLE	EACH	11		11
*81400115	HANDHOLE TO BE ADJUSTED	EACH	16		16
*81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	21,000		21,000
*81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	8,250		8,250
*81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	500		500
*81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	225		225
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3,100		3,100
*82500505	LIGHTING CONTROLLER, SPECIAL	EACH	2		2
*83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	270		270
*83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	70		70
*84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	8		8
*84200700	LIGHTING FOUNDATION REMOVAL	EACH	8		8
*84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3		3
*87800215	CONCRETE FOUNDATION, TYPE D	FOOT	4		4
*89502380	REMOVAL OF EXISTING HANDHOLE	EACH	21		21
*X0539800	TREE GRATES	EACH	16		16
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	9		9
XX002948	TEMPORARY ACCESS WALK	EACH	44		44
XX003219	UNIT PAVERS	SQ FT	25,569		25,569
XX004869	UNIT PAVERS, TACTILE	SQ FT	150		150
*XX006937	GROUND ROD, 5/8" DIA, X 10 FT	EACH	39		39
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1

SUMMARY OF QUANTITIES					
ITEM CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	Y003	Y030-1E
Z0076600	TRAINEES	HOUR	500	500	
XX005064	CLASS D PATCHES	SQ YD	883	883	
XX007448	CONCRETE EDGING, 6" WIDE	FOOT	286	286	
XX007449	CONCRETE EDGING, 12" WIDE	FOOT	1,837	1,837	
XX006805	PORTLAND CEMENT CONCRETE BASE COURSE, 4 INCH SPECIAL	SQ FT	24,969	24,969	
XX007450	*ORNAMENTAL LIGHT POLE, INSTALL ONLY	EACH	33		33
XX001136	*LIGHT POLE, SPECIAL	EACH	3		3
X0321766	*LIGHT POLE, SPECIAL (DECORATIVE ORNAMENTAL)	EACH	1		1
XX007451	*STREET TREE LIGHTING SYSTEM	EACH	13		13
XX001621	BRICK PAVER REMOVAL	SQ FT	4500	4,500	
XX007454	RAISED PLANTERS REMOVAL	FOOT	250	250	
XX007456	*UTILITY TRENCH - WATER SUPPLY	FOOT	150	150	
X0322983	STONE CURB	FOOT	40	40	
XX007209	*SKATEBOARD DETERRENT	FOOT	20	20	
XX007457	FLAGSTONE PAVERS	SQ FT	250	250	
XX007458	STONE WALL - SINGLE SIDED	FOOT	236	236	
XX007459	STONE WALL - DOUBLE SIDED	FOOT	40	40	
XX007460	STONE PIER	EACH	7	7	
XX007461	*OUTCROPPING	FOOT	70	70	
XX007462	*STEEL PLANTER BOXES	FOOT	110	110	
X0301571	*GATES, SPECIAL	EACH	4	4	
XX007465	*STEEL FENCE PANELS	FOOT	185	185	
XX007466	*BENCH 6'	EACH	22	22	
XX007467	*BENCH 4'	EACH	5	5	
XX000959	*TRASH RECEPTACLES	EACH	4	4	
XX007468	*PEDESTRIAN STREET LIGHT	EACH	3		3
XX007469	*UPLIGHTS	EACH	24		24
XX003308	*TRENCH DRAINS	FOOT	60	60	
XX007470	*PVC STORM PIPE / UNDERDRAINAGE	FOOT	500	500	
XX007471	*WATER TAP	EACH	1	1	
XX007472	*ORNAMENTAL GRASSES	UNIT	6	6	
XX007473	*GROUND COVER	UNIT	70	70	
XX005856	*MULCH-SHARDEDDED HARDWOOD BARK, 3" Depth	CU YD	32	32	
XX004533	*SOIL PLANTING MIXTURE	CU YD	115	115	
XX005967	*TOPSOIL (PLANTING MIXTURE)	CU YD	50	50	
XX007474	*SITE ELECTRIC - DESIGN AND BUILD	EACH	2		2
XX003885	*IRRIGATION SYSTEM	L SUM	1	1	
XX007475	FOUNTAIN REMOVAL	L SUM	1	1	

* SPECIALTY ITEMS

Δ Y030

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS			
ITEM DESCRIPTION	DEPTH (IN)	EXCAVATION (CU YD)	
UNIT PAVERS	25,569	SQ FT	552.4
UNIT PAVERS, TACTILE	150	SQ FT	3.3
SODDING, SPECIAL	187	SQ YD	20.8
MISC SITE WORK			83.3
TOTAL REMOVAL AND DISPOSAL OF UNSUITABLES =			659.8

REVISIONS	
NAME	DATE
IDOT COMMENTS	3/27/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. 2678
YORK ROAD

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 12/22/07

DRAWN BY: RAJ
CHECKED BY: JDM