

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2560	08-00139-00-RS	DUPAGE	22	2
STA. N/A	TO STA. N/A			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**CONTRACT NO. 63030**

**GENERAL NOTES**

**SPECIFICATIONS, STANDARDS AND SPECIAL PROVISIONS:**

ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007. (HEREINAFTER REFERRED TO AS THE STANDARD SPECIFICATIONS); THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", ADOPTED JAN. 1, 2008; THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS; THE "DETAILS" ON THE PLANS AND THE "SPECIAL PROVISIONS" INCLUDED IN THE CONTRACT DOCUMENTS. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED AS THE LATEST STANDARD OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.

**PROJECT COORDINATION**

THE CONTRACTOR SHALL NOTIFY THE CITY ENGINEER AT LEAST 72 HOURS IN ADVANCE OF BEGINNING WORK AND SHALL COORDINATE ALL CONSTRUCTION OPERATIONS WITH THE ENGINEER. ATTENTION IS CALLED TO SECTION 701 OF THE STANDARD SPECIFICATIONS AND THE SPECIAL PROVISIONS FOR TRAFFIC CONTROL AND PROTECTION. THE STORAGE OF EQUIPMENT AND/OR MATERIALS WITHIN THE RIGHT-OF-WAY SHALL REQUIRE PRIOR APPROVAL OF THE ENGINEER.

**SAFETY**

ALL CONSTRUCTION PERSONNEL WILL BE REQUIRED TO WEAR FLUORESCENT ORANGE SAFETY VESTS AT ALL TIMES WHILE ON THE CONSTRUCTION SITE.

**EXISTING UTILITIES:**

EXISTING UTILITIES ARE SHOWN ON THE PLANS ACCORDING TO INFORMATION OBTAINED FROM THE CITY OF NAPERVILLE AND FIELD SURVEYS. THE ACCURACY AND COMPLETENESS OF SAID INFORMATION IS NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE EXISTENCE, NATURE AND EXACT LOCATIONS OF ALL UTILITY LINES AND APPURTENANCES WITHIN THE LIMITS OF THE IMPROVEMENTS. THE CONTRACTOR SHALL GIVE PRIOR NOTIFICATION TO THE UTILITY COMPANIES AND THE CITY OF NAPERVILLE OF HIS INTENTION TO BEGIN WORK.

CERTAIN EXISTING UTILITY FACILITIES WHICH INTERFERE WITH THE PROPOSED CONSTRUCTION WILL HAVE TO BE REMOVED AND RELOCATED BY THE UTILITY COMPANIES OR THE CITY OF NAPERVILLE. THE CONTRACTOR SHALL COORDINATE AND SCHEDULE PROPOSED WORK WITH ALL AFFECTED UTILITY COMPANIES AND THE CITY OF NAPERVILLE SO AS TO INSURE THE TIMELY COMPLETION AND MAINTENANCE OF SAID UTILITY FACILITIES.

THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR INTERFERENCE WITH OR DAMAGE TO ANY EXISTING UTILITY FACILITY AND APPURTENANCES SUCH AS WATER MAINS, SEWERS, GAS MAINS, ELECTRIC AND SIGNAL CABLES, CONDUITS, ETC., RESULTING FROM THE OPERATIONS OF THE CONTRACTORS EQUIPMENT OR EMPLOYEES AND SHALL REPAIR OR REPLACE SAME AT THE CONTRACTORS EXPENSE AND WITH THE LEAST POSSIBLE DELAY. NO EXTRA COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR FOR ANY EXPENSES INCURRED BECAUSE OF DELAYS, INCONVENIENCES OR INTERRUPTIONS TO HIS WORK RESULTING FROM COMPLIANCE WITH THE ABOVE REQUIREMENTS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CALLING J.U.L.I.E. AT TOLL FREE NUMBER 800-892-0123 REQUESTING UTILITY LOCATION STAKING PRIOR TO EXCAVATING.

**TRAFFIC CONTROL AND MAINTENANCE:**

THE CONTRACTOR SHALL SCHEDULE HIS WORK SO THAT ONLY ONE TEMPORARY LANE CLOSURE IN EACH DIRECTION IS IMPLEMENTED AT A TIME. A LANE CLOSURE WILL ONLY BE PERMITTED DURING CONSTRUCTION OPERATIONS AND IN ACCORDANCE WITH THE APPLICABLE IDOT STANDARD. THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN ALL SIGNS, BARRICADES AND OTHER TRAFFIC CONTROL DEVICES INCLUDING FLAGGERS REQUIRED TO MAINTAIN TRAFFIC FLOW. THE CONTRACTOR SHALL SCHEDULE HIS WORK SO THAT NO HOLES IN THE PAVEMENT REMAIN OPEN OVER NIGHT.

ACCESS TO ABUTTING PROPERTY SHALL BE PROVIDED AT ALL TIMES DURING CONSTRUCTION OF THIS PROJECT. TIME REQUIRED FOR CONSTRUCTION AT DRIVEWAYS SHALL BE LIMITED TO THE MINIMUM TIME REQUIRED FOR SAID CONSTRUCTION AND, IF REQUIRED, TEMPORARY AGGREGATE SURFACE FOR DRIVEWAY ACCESS SHALL BE PROVIDED.

**STATE STANDARDS**

STANDARD NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
424001-05	CURB RAMPS FOR SIDEWALK
442201-03	CLASS C AND D PATCHES
606001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701501-04	URBAN LANE CLOSURE, 2L, 2W UNDIVIDED
701701-05	URBAN LANE CLOSURE MULTILANE INTERSECTION
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901	TRAFFIC CONTROL DEVICES
780001-01	TYPICAL PAVEMENT MARKINGS
886001	DETECTOR LOOP INSTALLATIONS
886006	TYPICAL LAYOUTS FOR DETECTION LOOPS

**DISPOSAL OF EXCESS MATERIAL:**

ALL EXCESS MATERIAL AND ANY OTHER DEBRIS SHALL BE DISPOSED OF BY THE CONTRACTOR AT AN OFF-SITE DISPOSAL AREA.

**PROTECTION OF PUBLIC/PRIVATE PROPERTY:**

THE CONTRACTOR SHALL PROTECT ALL EXISTING TREES, SHRUBS, FENCES, DRAIN LINES, POWER LINES, AND OTHER PUBLIC/PRIVATE PROPERTY. ANY ITEM THAT IS DAMAGED SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER AT NO ADDITIONAL COST TO THE CONTRACT.

**SAW CUTTING FOR REMOVAL:**

THE CONTRACTOR SHALL BE REQUIRED TO MAKE A FULL DEPTH SAW CUT AT THE EDGE OF PAVEMENT ADJACENT TO THE REMOVAL OF ALL CONCRETE CURB OR COMBINATION CONCRETE CURB AND GUTTER. THE CONTRACTOR SHALL MAKE ALL FULL DEPTH SAW CUTS REQUIRED FOR THE REMOVAL OF CONCRETE CURB AND GUTTERS, SIDEWALKS AND DRIVEWAYS AS SPECIFIED, OR AS DIRECTED BY THE ENGINEER. THE COST SHALL BE CONSIDERED INCLUDED IN THE COST FOR REMOVAL OF THE SPECIFIED ITEM IN THE CONTRACT.

**EXISTING STREET CLEANLINESS:**

THE CONTRACTOR SHALL KEEP EXISTING ADJACENT STREETS CLEAN OF DIRT, MUD, AND OTHER DEBRIS AND, WHEN NECESSARY, CLEAN SAID PAVEMENTS ON A DAILY BASIS OR WHEN DIRECTED BY THE ENGINEER.

**BASE COURSE CLEANING:**

PRIOR TO APPLYING THE HOT-MIX ASPHALT PRIME COAT, THE BASE SURFACE INCLUDING GUTTERS SHALL BE CLEANED OF LOOSE GRINDINGS, LEAVES, OF ALL DUST, DIRT, WEEDS AND OTHER FOREIGN MATERIALS. ALL CRACK FILL MATERIAL SHALL BE REMOVED IN ITS ENTIRETY ALONG THE CURB LINE. COST TO BE CONSIDERED INCLUDED IN THE COST OF THE HOT-MIX ASPHALT SURFACE WORK.

**BASE PATCHING AND REPAIR**

PRIOR TO THE PLACEMENT OF PATCHES FOR BASE REPAIR, THE SUBGRADE SHALL BE INSPECTED BY THE ENGINEER. IF ADDITIONAL SUBBASE REPAIR IS NECESSARY, THE AREA SHALL BE UNDERCUT AND BACKFILLED WITH P.G.E. MATERIAL AS APPROVED BY THE ENGINEER. THE UNDERCUTTING, REMOVAL, HAULING AND DISPOSAL OF THE UNSUITABLE MATERIAL WILL NOT BE MEASURED AND PAID SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE ITEM OF POROUS GRANULAR EMBANKMENT, SUBGRADE AS REQUIRED BY THE ENGINEER.

**CLEAN-UP AND DISPOSAL:**

THE CONTRACTOR SHALL MAINTAIN THE SITE IN A CLEAN AND ORDERLY MANNER. DEBRIS AND ANY SURPLUS MATERIAL SHALL BE REMOVED AND RESTORATION SHALL PROCEED AS THE WORK PROCEEDS. IF THE OWNER OR THE ENGINEER SO DIRECTS, THE CONTRACTOR SHALL STOP ALL OTHER WORK AND CONCENTRATE ON CLEAN-UP AND RESTORATION. DEBRIS AND SURPLUS MATERIAL SHALL BE DISPOSED OF BY THE CONTRACTOR OFF-SITE.

**CONSTRUCTION LIMITS:**

THE CONTRACTOR SHALL CONFINE OPERATIONS WITHIN THE DEDICATED ROADWAY RIGHTS-OF-WAY. ANY DAMAGE OUTSIDE OF SAID RIGHTS-OF-WAY SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

**LANDSCAPING RESTORATION:**

ALL LANDSCAPING DAMAGED DURING CONSTRUCTION SHALL BE RESTORED WITH A MINIMUM OF 4" OF PULVERIZED TOP SOIL AND SEEDING CLASS, 2A THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN COMBINATION . CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT, OR SIDEWALK REPLACEMENT.

**CURB AND GUTTER REPLACEMENT:**

THE MINIMUM THICKNESS OF THE PROPOSED GUTTER FLAG SHALL BE 10" UNLESS OTHERWISE STATED IN THE PLANS OR DIRECTED BY THE ENGINEER.

DISTURBED PAVEMENT AND GROUND AREAS SHALL BE RESTORED IMMEDIATELY FOLLOWING REPLACEMENT OPERATIONS, IN ALL CASES WITHIN THREE (3) WORKING DAYS FROM THE DATE THE CURB AND GUTTER WAS CAST. THE ENGINEER SHALL STOP THE CONTRACTOR FROM FURTHER REMOVAL OPERATIONS AT ANY TIME HE DETERMINES THE RESTORATION IS NOT BEING DONE IN A TIMELY MANNER. FAILURE TO COMPLY WITH THESE REQUIREMENTS SHALL RESULT IN THE ENFORCEMENT OF LIQUIDATED DAMAGES IN THE AMOUNT SPECIFIED IN ARTICLE 108.09 OF THE STANDARD SPECIFICATIONS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 NAPER BOULEVARD  
 GENERAL NOTES & STANDARDS  
 DRAWN BY: SDJ  
 DATE: Apr 11, 2008  
 CHECKED BY: DDL