

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2560	08-00139-00-RS	DUPAGE	22	3
STA.	N/A	TO STA.	N/A	
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CONTRACT NO. 63030

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY (1000)
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	667	667
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	667	667
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3987	3987
40600300	AGGREGATE (PRIME COAT)	TON	80	80
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	100	100
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	720	720
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	308	308
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4465	4465
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	200	200
42400800	DETECTABLE WARNINGS	SQ FT	40	40
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	39865	39865
44000600	SIDEWALK REMOVAL	SQ FT	200	200
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1600	1600
44002211	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 3/4"	SQ YD	2000	2000
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	500	500
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	500	500
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	500	500
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	500	500
60300310	FRAME AND LID TO BE ADJUSTED (SPECIAL)	EACH	55	55
60261700	INLETS TO BE ADJUSTED WITH NEW TYPE B-24 FRAME AND GRATE	EACH	2	2
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MON	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10125	10125
△ 70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	220	220
△ 70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	40575	40575
△ 70300635	TEMPORARY PAINT PAVEMENT MARKING - LINE 6"	FOOT	325	325
△ 70300645	TEMPORARY PAINT PAVEMENT MARKING - LINE 12"	FOOT	165	165
△ 70300660	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"	FOOT	165	165
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	220	220
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40575	40575
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	325	325
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	165	165
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	165	165

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY (1000)
△ 88600600	DETECTOR LOOP, REPLACEMENT	FOOT	930	930
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1675	1675
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL & REPLACEMENT	SQ YD	150	150
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	2	2
Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	5	5
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
* Z0076600	TRAINEES	HOUR	500	500

* Y080

△ DENOTE SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION NAPER BOULEVARD
NAME	DATE	
		<p style="font-size: 12px; margin: 0;">SUMMARY OF QUANTITIES</p> <p style="font-size: 8px; margin: 0;">DRAWN BY: SDJ</p> <p style="font-size: 8px; margin: 0;">DATE: Apr 11, 2008</p> <p style="font-size: 8px; margin: 0;">CHECKED BY: DDL</p>