

F.A.S. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1505	08-00083-00-RS	COOK	012	002
STA.	TO STA.			
FED. ROAD DIST. NO.	KLIMBER	FED. AID PROJECT		

CONTRACT # 63038

S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	PAVEMENT	MARKINGS	LANDSCAPE
					CONSTRUCTION TYPE CODE		
					I000	SFTY-1D	Y003
	20101700	SUPPLEMENTAL WATERING	UNIT	1			1
	21101615	TOPSOIL, FURNISH AND PLACE, 4"	SQ YD	50			50
	25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	1			1
	25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	1			1
	25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	1			1
	25200110	SODDING, SALT TOLERANT	SQ YD	50			50
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	48	48		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1584	1584		
	40600300	AGGREGATE (PRIME COAT)	TON	20	20		
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	383	383		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL -- BUTT JOINT	SQ YD	150	150		
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	50	50		
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	810	810		
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	750	750		
	42400800	DETECTABLE WARNINGS	SQ FT	120	120		
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	10407	10407		
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	48	48		
	44000600	SIDEWALK REMOVAL	SQ FT	750	750		
	44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1003	1003		
	44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	300	300		
	44201725	CLASS D PATCHES, TYPE I, 7 INCHES	SQ YD	69	69		
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	116	116		
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	18	18		
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	8	8		
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1		
	67100100	MOBILIZATION	L SUM	1	1		
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	480		480	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	550		550	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	218		218	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	160		160	
	XX004847	STONE DRIVEWAY REMOVAL	SQ YD	10	10		
	XX004848	STONE DRIVEWAY REPLACEMENT	SQ YD	10	10		

* - INDICATES SPECIALTY ITEMS

- GENERAL NOTES:**
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
 - UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
 - IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
 - SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
 - ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
 - THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

119TH STREET
STREET RESURFACING
SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE 12-26-07
DRAWN BY PS/RG
CHECKED BY TRL

ROBINSON ENGINEERING, LTD.
1320 SOUTH PARK AVENUE, SOUTH HOLLAND, ILLINOIS 60473
(708) 321-8700 FAX (708) 321-8888
ILLINOIS DESIGN FIRM REGISTRATION NO. 18600128 07812-QUAN-01