

# SUMMARY OF QUANTITIES

CONTRACT NO. 64292				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3HBR-2	WINNEBAGO	171	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	US 20 J000 80% FED 20% STATE	BRIDGE X271-2A 80% FED 20% STATE
20200100	EARTH EXCAVATION	CU YD	8040	8040	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	<b>227</b>		<b>227</b>
25000210	SEEDING, CLASS 2A	ACRE	5.50	5.50	
25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	495	495	
25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	495	495	
25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	495	495	
25000750	MOWING	ACRE	5.50	5.50	
25100115	MULCH, METHOD 2	ACRE	5.50	5.50	
25100630	EROSION CONTROL BLANKET	SQ YD	2313	2313	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	6800	6800	
28000400	PERIMETER EROSION BARRIER	FOOT	5000	5000	
28000500	INLET AND PIPE PROTECTION	EACH	9	9	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	8454	8454	
31200100	STABILIZED SUB-BASE 4"	SQ YD	935	935	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	428	428	
40600990	TEMPORARY RAMP	SQ YD	111	111	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	939	939	
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "E", N 90	TON	973	973	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	3403	3403	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	690	690	
42001200	PAVEMENT FABRIC	SQ YD	3117	3117	

• SPECIALTY ITEM ● 100% STATE

PLOT DATE = Thu Mar 13 13:02:11 2008  
 FILE NAME = c:\prowork\64292\qtbl0278pl.dgn  
 USER NAME = drowid