

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3HR-2	WINNEBAGO	171	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	US 20 J000 80% FED 20% STATE	BRIDGE X271-2A 80% FED 20% STATE
50500505	STUD SHEAR CONNECTORS	EACH	12672		12672
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	192,510		192,510
50800515	BAR SPLICERS	EACH	1,742		1,742
51205200	TEMPORARY SHEET PILING	SQ FT	554		554
51500100	NAME PLATES	EACH	2		2
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	32		32
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	32		32
52100520	ANCHOR BOLTS, 1"	EACH	128		128
52100540	ANCHOR BOLTS, 1 1/2"	EACH	32		32
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	64	64	
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	66	66	
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	193	193	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54215547	METAL END SECTIONS 12"	EACH	4	4	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	163		163
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1.2	1.2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	166.5	166.5	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	309		309
• 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	750	750	
• 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	

• SPECIALTY ITEM

PLOT DATE = Fri Mar 14 09:53:47 2008
 FILE NAME = c:\p\projects\p2002\98\4852\89pl.dgn
 USER = jrb
 USER NAME = jrb