

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3HR-2	WINNEBAGO	171	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

25000600	POTASSIUM FERTILIZER NUTRIENTS	POUNDS	LOCATION	OFFSET	REMARKS
			US 20		
			US 20		
45.0			988 + 00.0 TO 999 + 00.0		
			STAGE 1 IL 251		
22.5			244 + 50.0 TO 260 + 50.0		
			IL 251		
45.0			245 + 50.0 TO 260 + 50.0		
			RAMP BD		
22.5			2510 + 50.0 TO 2513 + 50.0		
			RAMP AC		
22.5			2411 + 00.0 TO 2413 + 50.0		
			EXISTING RAMP DB		
22.5			2519 + 00.0 TO 2524 + 50.0		
			PROPOSED RAMP DB		
45.0			2516 + 00.0 TO 2519 + 50.0		
			EXISTING RAMP BC		
45.0			2603 + 00.0 TO 2611 + 00.0		
			EXISTING RAMP AD		
45.0			2006 + 50.0 TO 2015 + 50.0		
			TEMP RAMP AC		
45.0			30 + 00.0 TO 37 + 00.0		
45.0			30 + 00.0 TO 37 + 00.0		AFTER TEMP PAV'T REMOVAL
			TEMP RAMP BD		
45.0			10 + 00.0 TO 18 + 00.0		
45.0			10 + 00.0 TO 18 + 00.0		AFTER TEMP PAV'T REMOVAL
495.0			TOTAL		

25100115	MULCH METHOD 2	ACRE	LOCATION	OFFSET	REMARKS
			US 20		
0.50			988 + 00.0 TO 999 + 00.0		
			STAGE 1 IL 251		
0.25			244 + 50.0 TO 260 + 50.0		
			IL 251		
0.50			245 + 50.0 TO 260 + 50.0		
			RAMP BD		
0.25			2510 + 50.0 TO 2513 + 50.0		
			RAMP AC		
0.25			2411 + 00.0 TO 2413 + 50.0		
			EXISTING RAMP DB		
0.25			2519 + 00.0 TO 2524 + 50.0		
			PROPOSED RAMP DB		
0.50			2516 + 00.0 TO 2519 + 50.0		
			EXISTING RAMP BC		
0.50			2603 + 00.0 TO 2611 + 00.0		
			EXISTING RAMP AD		
0.50			2006 + 50.0 TO 2015 + 50.0		
			TEMP RAMP AC		
0.50			30 + 00.0 TO 37 + 00.0		
0.50			30 + 00.0 TO 37 + 00.0		AFTER TEMP PAV'T REMOVAL
			TEMP RAMP BD		
0.50			10 + 00.0 TO 18 + 00.0		
0.50			10 + 00.0 TO 18 + 00.0		AFTER TEMP PAV'T REMOVAL
5.50			TOTAL		

25000750	MOWING	ACRE	LOCATION	OFFSET	REMARKS
			US 20		
0.50			988 + 00.0 TO 999 + 00.0		
			STAGE 1 IL 251		
0.25			244 + 50.0 TO 260 + 50.0		
			IL 251		
0.50			245 + 50.0 TO 260 + 50.0		
			RAMP BD		
0.25			2510 + 50.0 TO 2513 + 50.0		
			RAMP AC		
0.25			2411 + 00.0 TO 2413 + 50.0		
			EXISTING RAMP DB		
0.25			2519 + 00.0 TO 2524 + 50.0		
			PROPOSED RAMP DB		
0.50			2516 + 00.0 TO 2519 + 50.0		
			EXISTING RAMP BC		
0.50			2603 + 00.0 TO 2611 + 00.0		
			EXISTING RAMP AD		
0.50			2006 + 50.0 TO 2015 + 50.0		
			TEMP RAMP AC		
0.50			30 + 00.0 TO 37 + 00.0		
0.50			30 + 00.0 TO 37 + 00.0		AFTER TEMP PAV'T REMOVAL
			TEMP RAMP BD		
0.50			10 + 00.0 TO 18 + 00.0		
0.50			10 + 00.0 TO 18 + 00.0		AFTER TEMP PAV'T REMOVAL
5.50			TOTAL		

25100630	EROSION CONTROL BLANKET	SQ YD	LOCATION	OFFSET	REMARKS
			IL 251		
2313			244 + 50.0 TO 264 + 08.0		REMOVAL AREA OF RAMP DB
2313			TOTAL		

28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	LOCATION	OFFSET	REMARKS
			US 20		
800			988 + 00.0 TO 999 + 00.0		ASSUME 16 APPLICATIONS
			STAGE 1 IL 251		
400			244 + 50.0 TO 260 + 50.0		ASSUME 16 APPLICATIONS
			IL 251		
400			245 + 50.0 TO 260 + 50.0		ASSUME 16 APPLICATIONS
			RAMP BD		
400			2510 + 50.0 TO 2513 + 50.0		ASSUME 16 APPLICATIONS
			RAMP AC		
400			2411 + 00.0 TO 2413 + 50.0		ASSUME 16 APPLICATIONS
			EXISTING RAMP DB		
400			2519 + 00.0 TO 2524 + 50.0		ASSUME 16 APPLICATIONS
			PROPOSED RAMP DB		
800			2516 + 00.0 TO 2519 + 50.0		ASSUME 16 APPLICATIONS
			EXISTING RAMP BC		
800			2603 + 00.0 TO 2611 + 00.0		ASSUME 16 APPLICATIONS
			EXISTING RAMP AD		
800			2006 + 50.0 TO 2015 + 50.0		ASSUME 16 APPLICATIONS
			TEMP RAMP AC		
800			30 + 00.0 TO 37 + 00.0		ASSUME 16 APPLICATIONS
			TEMP RAMP BD		
800			10 + 00.0 TO 18 + 00.0		ASSUME 16 APPLICATIONS
800			TOTAL		

PLOT DATE = Fri Mar 14 09:31:48 2008  
 FILE NAME = c:\pvc\joe\15\2082\8\ub03298.apl.dgn  
 PLOT SCALE = 1/8" = 1' IN.  
 USER NAME = joesad