

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	3HBR-2	WINNEBAGO	171	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

70301000	WORKZONE PAVEMENT MARKING REMOVAL			REMARKS
SQ FT	LOCATION	OFFSET		
93.6	TEMPORARY LETTERS & SYMBOLS			
18116.1	TEMPORARY - LINE 4" & TAPE TY III 4"			
493	TEMPORARY - LINE 8"			
284	TEMPORARY - LINE 12"			
264	TEMPORARY - LINE 24"			
19251	TOTAL			

70400100	TEMPORARY CONCRETE BARRIER			REMARKS
FOOT	LOCATION	OFFSET		
	US 20			
875.0	988 + 10.2 TO 996 + 85.6	EB		STAGE 2
862.5	990 + 13.8 TO 998 + 76.2	WB		STAGE 2
1737.5	TOTAL			

70400200	RELOCATE TEMPORARY CONCRETE BARRIER			REMARKS
FOOT	LOCATION	OFFSET		
762.5	987 + 61.6 TO 995 + 25.0	WB		STAGE 3
812.5	991 + 26.3 TO 999 + 38.6	EB		STAGE 3
1575.0	TOTAL			

78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS			REMARKS
SQ FT	LOCATION	OFFSET		
	IL 251			
62.0	264 + 00.0 TO 266 + 42.0			2 RT & 2 LT ARROWS
23.6	264 + 00.0 TO 266 + 42.0			2 SETS OF "ONLY" (6 FT)
11.5	AIRPORT DR			REPLACE THRU ARROW
97.1	TOTAL			

78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"			REMARKS
FOOT	LOCATION	OFFSET		
	US 20			
426.4	988 + 00.0 TO 992 + 26.4	LT - EB		YELLOW - EDGELINE
55.6	990 + 03.9 TO 992 + 26.4	EB		WHITE - SKIPDASH
210.0	990 + 16.4 TO 992 + 26.4	RT - WB		YELLOW - EDGELINE
52.5	990 + 16.4 TO 992 + 26.4	WB		WHITE - SKIPDASH
546.5	990 + 16.4 TO 992 + 26.4	LT - WB		WHITE - EDGELINE
545.9	991 + 25.1 TO 996 + 70.9	RT - EB		WHITE - EDGELINE
11.2	991 + 81.6 TO 992 + 26.4	EB		WHITE - SKIPDASH
5.6	992 + 03.9 TO 992 + 26.4	EB		WHITE - SKIPDASH
210.0	994 + 60.9 TO 996 + 70.9	LT - EB		YELLOW - EDGELINE
426.1	994 + 60.9 TO 998 + 87.0	RT - WB		YELLOW - EDGELINE
	IL 251 - NB			
551.6	244 + 90.3 TO 250 + 41.9	RT		WHITE - EDGELINE
2151.7	244 + 90.3 TO 266 + 42.0	LT		YELLOW - EDGELINE
537.9	244 + 90.3 TO 266 + 42.0			WHITE - SKIPDASH
37.1	252 + 42.2 TO 253 + 90.7	RT		WHITE - SKIPDASH
49.4	262 + 51.8 TO 264 + 00.0	RT		WHITE - SKIPDASH
36.2	262 + 91.4 TO 264 + 00.0	LT		WHITE - SKIPDASH (TURNLANE)
	IL 251 - SB			
2086.1	245 + 55.9 TO 266 + 42.0	RT		YELLOW - EDGELINE
521.5	245 + 55.9 TO 266 + 42.0			WHITE - SKIPDASH
317.0	245 + 55.9 TO 248 + 72.9	LT		WHITE - EDGELINE
31.6	252 + 14.4 TO 253 + 40.6	LT		WHITE - SKIPDASH
695.5	255 + 40.6 TO 262 + 36.1	LT		WHITE - EDGELINE
334.8	262 + 36.1 TO 265 + 70.9	LT		WHITE - EDGELINE (RAMP)

CONT. 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"			REMARKS
FOOT	LOCATION	OFFSET		
	RAMP BD			
232.4	2510 + 77.0 TO 2513 + 09.4	LT		YELLOW - EDGELINE
349.6	2510 + 77.0 TO 2514 + 26.6	RT		WHITE - EDGELINE
	RAMP AC			
208.3	2411 + 02.0 TO 2413 + 10.3	LT		YELLOW - EDGELINE
324.8	2411 + 02.0 TO 2414 + 26.8	RT		WHITE - EDGELINE
	RAMP DB			
300.8	2516 + 50.0 TO 2413 + 54.5	LT		YELLOW - EDGELINE
428.5	2516 + 50.0 TO 2413 + 54.5	RT		WHITE - EDGELINE
	RAMP BC			
788.9	2603 + 46.4 TO 2611 + 35.3	LT		YELLOW - EDGELINE
788.9	2603 + 46.4 TO 2611 + 35.3	RT		WHITE - EDGELINE
	RAMP AD			
835.8	2006 + 71.5 TO 2015 + 07.3	LT		YELLOW - EDGELINE
835.8	2006 + 71.5 TO 2015 + 07.3	RT		WHITE - EDGELINE
14934.0	TOTAL			

78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"			REMARKS
FOOT	LOCATION	OFFSET		
	US 20			
307.0	990 + 03.9 TO 992 + 03.9	RT - EB		WHITE - EDGELINE
185.0	990 + 16.4 TO 991 + 81.6	LT - WB		WHITE - EDGELINE
271.0	994 + 82.2 TO 996 + 83.3	LT - WB		WHITE - EDGELINE
218.0	994 + 86.6 TO 996 + 70.9	RT - EB		WHITE - EDGELINE
	IL 251			
531.7	248 + 72.9 TO 252 + 14.4	LT - SB		WHITE - EDGELINE
401.5	250 + 41.9 TO 252 + 42.2	RT - NB		WHITE - EDGELINE
397.8	253 + 40.6 TO 255 + 40.6	LT - SB		WHITE - EDGELINE
501.1	253 + 90.7 TO 257 + 15.3	RT - NB		WHITE - EDGELINE
411.0	262 + 36.1 TO 265 + 15.8	LT - SB		WHITE - EDGELINE
482.0	264 + 00.0 TO 266 + 42.0	RT & LT - NB		WHITE - TURNLANE
3706.1	TOTAL			

78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"			REMARKS
FOOT	LOCATION	OFFSET		
	IL 251			
58.0	266 + 42.0			
	RAMP DB			
25.7	2519 + 41.0			
83.7	TOTAL			

PLOT DATE = Fri, Mar 14 09:01:48 2008
 FILE NAME = c:\projects\2008\2008\2008\2008.dwg
 PLOT SCALE = 1/8" = 1' / IN.
 USER NAME = dward