

# SUMMARY OF QUANTITIES

80% Federal 20% State  
URBAN  
1000

80% Federal 20% State  
URBAN  
1000

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	202
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16
20101100	TREE TRUNK PROTECTION	EACH	2
20200100	EARTH EXCAVATION	CU YD	2370
* 25000100	SEEDING, CLASS 1	ACRE	0.5
* 25000210	SEEDING, CLASS 2A	ACRE	0.75
* 25000750	MOWING	ACRE	1.25
* 25100630	EROSION CONTROL BLANKET	SQ YD	4889
* 25200100	SODDING	SQ YD	3753
* 25200200	SUPPLEMENTAL WATERING	UNIT	34
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1780
28000300	TEMPORARY DITCH CHECKS	EACH	42
28000400	PERIMETER EROSION BARRIER	FOOT	810
28000500	INLET AND PIPE PROTECTION	EACH	7
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2099
35100100	AGGREGATE BASE COURSE, TYPE A	TON	3178
35101400	AGGREGATE BASE COURSE, TYPE B	TON	353
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	1721
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.0
40600300	AGGREGATE (PRIME COAT)	TON	14
40600535	LEVELING BINDER (HAND METHOD), N70	TON	2.3
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	353
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	310
40600990	TEMPORARY RAMP	SQ YD	52
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	141
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	445
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	88
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2690
44004250	PAVED SHOULDER REMOVAL	SQ YD	1837
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3405
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1847
50800105	REINFORCEMENT BARS	POUND	42
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	13

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	280
54213450	END SECTIONS 15"	EACH	14
54248510	CONCRETE COLLAR	CU YD	1
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	100
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2
61140000	STORM SEWERS (SPECIAL) 8"	FOOT	100
61140100	STORM SEWERS (SPECIAL) 10"	FOOT	100
61140200	STORM SEWERS, SPECIAL 12"	FOOT	100
63500105	DELINEATORS	EACH	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	504
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	56
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	188
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9645
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	801
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	328
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	25
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	36
* D2003872	EVERGREEN, THUJA OCCIDENTALIS TECHN (TECHNY ARBORVITAE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	29
XX003437	REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS	EACH	1
X0325911	HOT-MIX ASPHALT SURFACE COURSE, SPECIAL	TON	300
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	9
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	1000

\* SPECIALTY ITEMS

NP- 100% STATE

FILE NAME = c:\projects\p289684\d09684\cvr.dgn	USER NAME = polzinej	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1/8" = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Tue Mar 11 07:37:43 2008	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 754	SECTION 101M	COUNTY BOONE	TOTAL SHEETS 48	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 64A45	