

SCHEDULE OF QUANTITIES

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION
1	50' LT 1141+00
1	70' LT 1145+00
1	70' LT 1149+00
1	55' LT 1150+00
4	TOTAL

PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION
2	Contact Resident Engineer or Mike Blumhoff
2	TOTAL

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION
15.6	Sta 1143+58.2 Right Turn Arrow
15.6	Sta 1144+33.2 Right Turn Arrow
15.6	Sta 1145+8.2 Right Turn Arrow
15.6	Sta 1145+84.4 Right Turn Arrow
15.6	Sta 1147+56.5 Left Turn Arrow
15.6	Sta 1148+31.5 Left Turn Arrow
15.6	Sta 1149+6.3 Left Turn Arrow
15.6	Sta 1149+81.4 Left Turn Arrow
15.6	Sta 1152+70.8 Right Turn Arrow
15.6	Sta 1153+40.8 Right Turn Arrow
15.6	Sta 1154+10.8 Right Turn Arrow
15.6	Sta 1154+80.8 Right Turn Arrow
187.2	TOTAL

THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
<u>IL RTE 76</u>	
812.2	Rt. Sta 1139+45 - 11+46 WHITE EDGE
2568.1	Sta 1139+45 - 1146+33 YELLOW MEDIAN
755.3	Rt. Sta 10+80 - 1154+88 WHITE EDGE
3111.8	Sta 1147+30 - 1155+06 YELLOW MEDIAN
1559.1	Lt. Sta 1139+45 - 1155+06 WHITE EDGE
<u>Walnut Grove</u>	
395	Lt. Sta 10+80 - 14+75 WHITE EDGE
333	Rt. Sta 11+42 - 14+75 WHITE EDGE
110	Sta 10+50 - 14+75 YEL SKIP
9644.5	TOTAL

THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION
285.7	Sta 1143+43 - 1146+29 Rt. Turn Lane
264.7	Sta 1147+31 - 1149+96 Lt. Turn Lane
250	Sta 1152+56 - 1155+06 Rt. Turn Lane
800.4	TOTAL

THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION
132.5	Sta 1139+95 - 1146+33 Yellow Median Diagonals
194.7	Sta 1150+63 - 1155+06 Yellow Median Diagonals
327.2	TOTAL

THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
24.3	Rt Sta 10+47 White Stop Bar
24.3	TOTAL

RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
100	Sta 1139+45 - 1152+61
100	TOTAL

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
36	Sta 1139+45 1151+80
36	TOTAL

EVERGREEN, THUJA OCCIDENTALIS TECHN (TECHNY ARBORVITAE), 6' HEIGHT, BALLED AND BURLAPPED

EACH	LOCATION
29	Sta 1148+00 1151+00 *See Landscape Architect
29	TOTAL

REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS

EACH	LOCATION
1	Rt Sta 1150+88
1	TOTAL

GEOTECHNICAL REINFORCEMENT

SQ YD	LOCATION
500	LT Sta. 1141+00 1145+50
500	RT Sta. 1141+00 1145+50
1000	TOTAL