

SUMMARY OF QUANTITIES

CONTRACT NO. 64C35

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
17	15T-2	CARROLL	71	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES				RURAL	
				Y007	Y007
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED/ 20%STATE	80% FED/ 20%STATE
40600990	TEMPORARY RAMP	SQ YD	184	76	108
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX"C", N50	TON	139	103	36
44004250	PAVED SHOULDER REMOVAL	SQ YD	240	240	
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	655	361	294
44213200	SAW CUTS	FOOT	443	443	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	57	57	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	976	633	343
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO.2	EACH	1	1	
50300225	CONCRETE STRUCTURES	CY YD	78	78	
50800105	REINFORCEMENT BARS	POUND	35,630	12,370	23,260
50901760	PIPE HANDRAIL	FOOT	37	37	
51205200	TEMPORARY SHEET PILING	SQ FT	5,224	3,513	1,711
51500100	NAME PLATES	EACH	3	2	1
54003000	CONCRETE BOX CULVERTS	CY YD	143		143
54010808	PRECAST CONCRETE BOX CULVERT 8' X 8'	FOOT	100	100	
54213717	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 72"	EACH	2	2	
54215550	METAL END SECTIONS 15"	EACH	4	4	
542A0277	PIPE CULVERTS, CLASS A, TYPE 1 72"	FOOT	83	83	
*SPECIALTY ITEMS					

PLOT DATE = Mon Jan 28 16:32:41 2008
 PLOT SCALE = 1/8" = 100'
 PLOT SIZE = 36" x 48"
 USER NAME = hennrichs