

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1177	(110,111)T	LEE	59	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	80% FED - 20% STATE Y007 TOTAL QUANTITY
61101020	STORM SEWERS PROTECTED, CLASS A, 18"	FOOT	160
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA,	EACH	4
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	2
63200310	GUARDRAIL REMOVAL	FOOT	1324
63500105	DELINEATORS	EACH	8
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	32
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	47172
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	32
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	68
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	41
X0323660	DROP BOX NO.1	EACH	1
X0323661	DROP BOX NO.2	EACH	1
X0323662	DROP BOX NO.3	EACH	1
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
X0712400	TEMPORARY PAVEMENT	SQ YD	196
Z0005400	BREAKER-RUN CRUSHED STONE	TON	900
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0023600	FILLING EXISTING CULVERTS	EACH	1

*SPECIALTY ITEMS

PLOT DATE = Tue Feb 26 13:09:48 2008
 FILE NAME = c:\p\proj\p05\p208187\dr0197ov.dgn
 PLOT SCALE = 0.25"=1'-0"
 USER NAME = csherman