

AGGREGATE /EARTHWORK SCHEDULE

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1177	(110,111)T	LEE	59	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LOCATION	REMARKS	WIDTH FOOT	AREA SQ FT	20005400 BREAKER RUN CRUSHED STONE		48101200	40800050	35101400	X0712400
				INCHES	TON	AGGREGATE SHOULDERS TYPE B	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE BASE COURSE TYPE B	TEMPORARY PAVEMENT
					TON	TON	TON	TON	SQ YD
IL 251									
Lt Sta	27+00 - 29+77	Agg. Shoulder	831			31.5			
Rt Sta	27+00 - 29+20	Agg. Shoulder	440			16.7			
Lt & Rt. Sta	259+50 - 263+50	Agg. Shoulder	2400			91.1			
Lt & Rt. Sta	274+50 - 282+00	Agg. Shoulder	4500			170.8			
Lt & Rt Sta	527+00 - 530+00	Agg. Shoulder	900			34.2			
Lt Sta	317+50 - 329+00	Agg. Shoulder	3450			131.0			
Culvert	261 + 52		1701	36"	387.5				
Culvert	277 + 15		2399	12"	182.1				
Culvert	528 + 47		2177	24"	330.6				
FE	325 + 10	24'	1895					95.9	
FE	326 + 50	24'	1620					82.0	
PE	328 + 58	24'	1042				16.2	52.7	
FE	529 + 70	24'	1038					52.5	
Lt Sta	27+00 - 29+77	STAGE 1	831			31.5			
Rt Sta	27+00 - 29+20	STAGE 2	440			16.7			
Detour Maintenance		Agg. Shoulder	50000			632.7			
US 30 / Brooklyn Rd.			1053						117.0
Spur Rd.			711						79.0
Total			60807		900	1156	16	283	196

LOCATION	20200100			
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)
27+00.00 TO 29+77.00	270.6	203.0	77.2	125.8
259+50.00 TO 263+50.00	489.2	366.9	515.6	-148.7
274+50.00 TO 282+00.00	1012.7	759.5	573.8	185.7
317+50.00 TO 329+00.00	1633.7	1225.3	42.5	1182.8
527+00.00 TO 530+00.00	416.7	312.5	162.3	150.2
TOTALS	3822.9	2867.2	1371.4	1495.8

PLOT DATE = Tue Feb 26 10:25:08 2008
 PLOT SCALE = 50.0000 / IN.
 USER NAME = cshamshv