

SUMMARY OF QUANTITIES

I-74 EB

URBAN
J000

PAY CODE	ITEM	UNIT	100% State QUANTITY
20200100	EARTH EXCAVATION	CU YD	1625
25000115	SEEDING, CLASS 1B	ACRE	1
25100115	MULCH, METHOD 2	ACRE	1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1300
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2750
44000100	PAVEMENT REMOVAL	SQ YD	2750
44004250	PAVED SHOULDER REMOVAL	SQ YD	2025
44213200	SAW CUTS	FOOT	176
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	2025
67100100	MOBILIZATION	L SUM	1
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	4232
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	38
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017202	DOWEL BARS 1 1/2"	EACH	1813

* SPECIALTY ITEM

FILE NAME = C:\Projects\p203008\403008shts.dgn	USER NAME = ditzlerse	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. -14-	SECTION (R)-385M-1	COUNTY ROCK ISLAND	TOTAL SHEETS 2	SHEET NO. 2
PLOT SCALE = 20,000' / 1" IL		CHECKED -	REVISED -	SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				
PLOT DATE = Wed Feb 27 14:33:30 2008		DATE -	REVISED -	CONTRACT NO. 64094						