

SCHEDULE OF QUANTITIES

20200100	EARTH EXCAVATION CU YD LOCATION 1625 313+57.10 TO 323+66.81 (UNDER PAVEMENT & SHLD) 1625 TOTAL	44213200	SAWCUTS FOOT LOCATION 126 323+66.81 EB 50 313+57.10 EB 176 TOTAL
25000115	SEEDING CLASS 1B ACERS LOCATION 1 PROJECT LIMITS 1 TOTAL	48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10" SQ YD LOCATION 675 313+57.10 TO 323+66.81 LT (6 FT) EB 1350 313+57.10 TO 323+66.81 RT (12FT) EB 2025 TOTAL
25100115	MULCH METHOD 2 ACERS LOCATION 1 PROJECT LIMITS 1 TOTAL	67100100	MOBILIZATION L SUM LOCATION 1 I-74 / 280 EB 1 TOTAL
28000250	TEMPORARY EROSION CONTROL SEEDING POUND LOCATION 400 PROJECT LIMITS 400 TOTAL	78005110	EPOXY PAVEMENT MARKING - LINE 4" FOOT LOCATION 1010 313+57.10 TO 323+66.81 LT (YELLOW) EB 1010 313+57.10 TO 323+66.81 RT (WHITE) EB 2212 313+57.10 TO 319+59.10 (PAINTED MEDIAN, WHITE) EB 4232 TOTAL
35100100	AGGREGATE BASE COURSE, TYPE A TON LOCATION 1300 313+57.10 TO 323+66.81 (&VARIOUS) 1300 TOTAL	78005140	EPOXY PAVEMENT MARKING - LINE 8" FOOT LOCATION 38 I-74 / 280 EB (PAINTED MEDIAN) 38 TOTAL
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) SQ YD LOCATION 1770 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 980 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2750 TOTAL	Z0013798	CONSTRUCTION LAYOUT L SUM LOCATION 1 PROJECT LIMITS 1 TOTAL
44000100	PAVEMENT REMOVAL SQ YD LOCATION 1770 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 980 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2750 TOTAL	Z0017202	DOWEL BARS 1 1/2" EACH LOCATION 1813 313+57.10 TO 323+66.81 1813 TOTAL
44004250	PAVED SHOULDER REMOVAL SQ YD LOCATION 675 313+57.10 TO 323+66.81 LT (16.5-15FT) EB 1350 313+57.10 TO 323+66.81 RT (16.5-1FT) EB 2025 TOTAL		

FILE NAME = C:\Projects\p203008\030808sta.dgn	USER NAME = dhtlorso	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE. 74	SECTION 1B1-3WSM-1	COUNTY ROCK ISLAND	TOTAL SHEETS 5	SHEET NO. 5
PLOT SCALE = 20.0000' / IN.		CHECKED -	REVISED -	SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT CONTRACT NO. 64094				
PLOT DATE = Wed Feb 27 14:33:13 2008		DATE -	REVISED -							