

FAP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	24.25RS-2	LIVINGSTON	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES				80% FED. 20% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION CODE	
			I000	TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD		86.4
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		12620.5
40600300	AGGREGATE (PRIME COAT)	TON		292.2
40600535	LEVELING BINDER (HAND METHOD), N70	TON		77
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON		6468.7
40600895	CONSTRUCTING TEST STRIP	EACH		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD		1401
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD		39.9
40600990	TEMPORARY RAMP	SQ YD		271.6
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON		12937.4
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON		471.6
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD		154016
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD		56
48101200	AGGREGATE SHOULDERS, TYPE B	TON		3726
66700095	PERMANENT SURVEY MARKERS	EACH		27
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		2
67100100	MOBILIZATION	L SUM		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM		1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT		13575.2
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		170
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT		99182.9
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT		11021.5
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT		770
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT		1115
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT		226
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		1506.9
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		170
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT		7208
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		770
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT		1115
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		226
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT		91974.9
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT		11021.5
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH		653
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH		653
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM		1

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_