

F.A. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(24,25)RS-2	LIVINGSTON	18	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVEMENT MARKINGS

LOCATION	LENGTH	PAINT PAVEMENT MARKINGS		THERMOPLASTIC PVMT MK						TEMPORARY PAINT PAVEMENT MARKINGS						SHORT TERM PVMT PAVEMENT MARKING	WORK ZONE PVMT MARKING REMOVAL		
		4"	6"	4"	8"	12"	24"	LETTERS & SYMBOLS	4"	6"	8"	12"	24"	LETTERS & SYMBOLS	SO FT.	SO FT.			
		WHITE LIN FT.	YELLOW LIN FT.	YELLOW LIN FT.	WHITE LIN FT.	WHITE LIN FT.	YELLOW LIN FT.	WHITE LIN FT.	WHITE SQ. FT.	WHITE LIN FT.	YELLOW LIN FT.	YELLOW LIN FT.	WHITE LIN FT.	WHITE LIN FT.	YELLOW LIN FT.	WHITE LIN FT.	SO FT.	SO FT.	
STA.502+00 TO 574+70.25	7270.25	14540.5	1817.6						14540.5		1817.6					2181.075	242.1		
BRIDGE OMISSION	22.75	45.5	10						45.5		10								
STA.574+93 TO 711+12.20	13619.2	27238.4	3404.8						27238.4		3404.8					4085.76	453.5		
STA.711+12.2 TO 747+02.6	3590.4	7180.8	897.6						7180.8		897.6					1077.12	119.6		
STA.747+02.6 TO 754+45	742.4	1484.8							1484.8										
STA.754+45 TO 761+30	685	1370							1370										
STA.761+30 TO 766+79.20	549.2	1098.4							1098.4										
STA. 766+79.20 TO 834+69.33	6790.13	13580.26	1697.5				72	123	13580.3		1697.5			72	123	2037.039	226.1		
BOX CULVERT 053-2034	20	40	10						40		10								
STA. 834+88.66 TO 912+62.83	7774.17	15548.34	1943.5						15548.3		1943.5					2332.251	258.9		
BRIDGE OMISSION	20.34	41	10						41		10								
STA. 912+83.17 TO 950+57.25	3774.08	7548.16	943.5						7548.16		943.5					1132.224	125.7		
BRIDGE OMISSION	21.5	43	10						43		10								
STA. 950+78.75 TO 961+86.60	1107.85	2215.7	277						2215.7		277					332.355	36.9		
FAS 342W INTERSECT.				7208	270		900	20	47		7208		270		900	20	47	119	13.2
4 TH ST. INTERSECT.					250	105		70					250	105		70		137	15.2
FAS 342E INTERSECT.					250	110		64					250	110		64		141.4	15.7
	45987.27	91974.9	11021.5	7208	770	215	900	226	170	91974.9	7208	11021.5	770	215	900	226	170	13575.224	1506.9

SIDEROAD SCHEDULE

STATION	SIDE	DESCRIPTION	MATERIAL	WIDTH	AREA	INCIDENTAL HOT-MIX ASPHALT SURFACE	BITUMINOUS PRIME COAT	AGGREGATE PRIME COAT	FURNISHED EXCAVATION	TEMPORARY RAMPS	HOT-MIX ASPHALT SURF.REM. BUTT JT.
				FOOT	SQ FT	TON	GAL	TON	CU YD	SQ YD	SQ YD
540+54.40	RT.	TR 2800 E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
540+54.40	LT.	TR 2800 E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
589+45	LT.	TR 244 C 2900E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
642+40	LT.	TR 248 C 3000E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
642+40	RT.	TR 248 C 3000E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
693+90	LT.	TR 254 C 3100E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
693+90	RT.	TR 254 C 3100E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
746+60	LT.	FR 1415 3200E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
746+60	RT.	TR 268 C 3200E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
760+00	LT.	FAS 342 W 3225E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
776+00	RT.	TR 225	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
776+20	LT.	TR 225	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
815+60	LT.	4 TH ST 3325E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
815+60	RT.	4 TH ST 3325E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
829+40	LT.	FAS 342 E 3350E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
829+40	RT.	FAS 342 E 3350E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
908+70	LT.	TR 282 B 3500E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
908+70	RT.	TR 282 B 3500E	BIT.	24	1320	18.5	11.7	0.3	4.8	13.3	53.3
LINE TOTAL						333	210.6	5.4	86.4	239.4	959.4

Apr 11, 2008 - 11:13:46 AM c:\projects\ed03604\cvs\sh - .dgn

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

REVISIONS	
NAME	DATE

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY