

SUMMARY OF QUANTITIES				URBAN 80% FED. 20% STATE
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		DEKALB ROADWAY
		UNIT	TOTAL QUANTITY	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	89	89
20400800	FURNISHED EXCAVATION	CU YD	12	12
25100630	EROSION CONTROL BLANKET	SQ YD	169	169
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	34	34
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6189	6189
40600300	AGGREGATE (PRIME COAT)	TON	144	144
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19	19
40600535	LEVELING BINDER (HAND METHOD), N70	TON	32	32
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2845	2845
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	603	603
40600990	TEMPORARY RAMP	SQ YD	826	826
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX ^D , N70	TON	5967	5967
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	562	562
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	14040	14040
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	59556	59556
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	80	80
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	18052	18052
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	295	295
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2960	2960
48203100	HOT-MIX ASPHALT SHOULDERS	TON	355	355
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	14	14
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18269	18269

SUMMARY OF QUANTITIES				URBAN 80% FED. 20% STATE
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		DEKALB ROADWAY
		UNIT	TOTAL QUANTITY	
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	2052.2	2052.2
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	39552	39552
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	9080	9080
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	6188	6188
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	1982	1982
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	1160	1160
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2010	2010
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1076.6	1076.6
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22360	22360
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6348	6348
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3283	3283
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1084	1084
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1019	1019
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	10128	10128
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1210	1210
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	936	936
* 78200300	PRISMATIC CURB REFLECTOR	EACH	16	16
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	361	361
88500100	INDUCTIVE LOOP DETECTOR	EACH	33	33
88600100	DETECTOR LOOP, TYPE I	FOOT	3707	3707
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	3	3
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
X8860100	LOOP DETECTOR TESTING	EACH	3	3
Z0024430	FLAGGER	HOUR	100	100
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEMS